



**MADERA UNIFIED
SCHOOL DISTRICT**
1902 Howard Road
Madera CA 93637
(559) 675-4500
(559) 675-1186 Fax
www.madera.k12.ca.us

Board of Trustees:

President:

Al Galvez

Clerk:

Robert E. Garibay

Trustees:

Ricardo Arredondo

Brent Fernandes

Ed McIntyre

Ray G. Seibert

Maria Velarde-Garcia

SUPERINTENDENT:

Edward C. González

October 20,2016

Addendum No. 1
Child Nutrition Walk-In Freezer Project
BID No. 101116

NOTICE TO ALL VENDORS:

This Addendum is attached to and made a part of the above entitled specifications for Madera Unified School District for BID No. 101116 with a due date of October 25th, 2016

Questions:

1. M1 calls for 7/8 RL and 2 1/8 RS but M2 detail AM-2 shows 1 3/8 RL and 2 1/8 RS at the coil.

At detail A/M-2 revise the RL line size to 7/8”.

2. S2.1 Detail 10 insulated floor shows insulation between pad and curb for a thermal break. Can we substitute a 2” x 12” pressure treated so I have something to attach my wall screed to or can I use an external angle to secure the wall panels in place?

On detail 10/S2.1, the thermal break is a requirement of freezer manufacturer. If a contractor wants to use a 2x12 PT nailer, the contractor will need to get approval from their freezer subcontractor. External angles may work, but this would also need to be reviewed by the freezer manufacturer along with the structural engineer once a revised detail is submitted.

See attached for location for Panel DP

Signature: _____

Print Name:_____

Date: _____