MADERA UNIFIED SCHOOL DISTRICT

1902 Howard Road, Madera, California 93637 (559) 675-4500 FAX: (559) 675-1186 www.madera.k12.ca.us



Board of Trustees:

Ruben Mendoza, President Brent Fernandes, Clerk **Trustees:** Ricardo Arredondo, Joetta Fleak, Ed McIntyre, Lucy Salazar, Ray G. Seibert

Superintendent: Todd Lile

March 23, 2020

Addendum No1. Bid No.031120-Re-Roofing Projects at Multiple School Sites

NOTICE TO ALL VENDORS:

This Addendum is attached to and made a part of the above-entitled specifications for Madera Unified School District for Bid No.031120-Re-Roofing Projects at Multiple School Sites with a Due date of April 3, 2020 no later than 1:30 p.m.

All changes and/or clarifications will appear in bold type and deletions will be struck out within a sentence. Questions/Clarifications:

New Bid Turn In process..

Changes to Bid Turn In

Due to the current and changing situation and to continue with work that is needed at our School Sites we have implemented changes as to how we are going to handle the Bid Turn In Process.

The District encourages vendors to submit bids in advance by mail and we will accept emailed bid packets.

The District will except emailed bid packets, they will only be accepted if it is sent to susanharautuneian@maderausd.org and it must be received no later than the date and time listed.

No public opening will take place at that time. MUSD staff will open all bids. Staff will recap the Bids and post the Bid Tally along with each contractors Bid Form on the District Website.

<u>Item #1</u> – Section 011100 Summary of Work, 1.3, E, 22; All downspouts are to remain and not be replaced. New gutters and downspout drops will be required into the existing downspout with a screen at each downspout location. All gutters at existing locations only will be removed and replaced with new. All gutter and drops are to be primed and painted.

<u>Item #2</u> – Section 011100 Summary of Work, 1.3, E, 21 & 32; All edge metal is to have a minimum 3.5" face dimension with 1/2" kick and hem. All metal edge is to be primed and painted.

<u>Item #3</u> – Section 011100 Summary of Work, 1.3, E, 6; Building B has exposed decking at the eve edges, it will be required to ensure fasteners are not showing on the underside of the roof deck. Insulation adhesive may be used in these areas as well as fasteners being applied directly into the purlins of the building both options are acceptable.

MADERA UNIFIED SCHOOL DISTRICT

1902 Howard Road, Madera, California 93637 (559) 675-4500 FAX: (559) 675-1186 www.madera.k12.ca.us



Board of Trustees:

Ruben Mendoza, President Brent Fernandes, Clerk **Trustees:** Ricardo Arredondo, Joetta Fleak, Ed McIntyre, Lucy Salazar, Ray G. Seibert

Superintendent: Todd Lile

<u>Item #4</u> – Section 011100 Summary of Work, 1.3, E, Add to the scope of work for Dixieland ES Building B. All duct work is to be cleaned, primed with Rust-Go Primer, and painted with Pyramic Acrylic coating.

<u>Item #5</u> – Section 011100 Summary of Work, 1.3, E, Add to the scope of work for both buildings A & B. At building B the antenna must remain in place, install 4"x6" wood blocks at each attachment location, install the roofing membrane over the blocks, install a 24 gauge galvanized cap then re-install the antenna. At building A install 4"x4" wood blocks, install a 24 gauge galvanized sheet metal pan over the block with a minimum 6" flange to install the new roof shingles.

<u>Item #6</u> – Section 011100 Summary of Work, 1.3, E, Add to the scope at building A, install 24 gauge galvanized sheet metal covers at each bracket holding up the canopy located at the eve edge as discussed at the pre bid meeting.

<u>Item #7</u> – Section 011100 Summary of Work, 1.3, E, 37; Delete the scope of work requiring removal and replacement of sheet metal flashings at all HVAC units and duct work. Inspect all existing sheet metal flanges, clean & prime all metal flanges, install new 24 gauge galvanized step flashing at the side of the roof curbs and install composition shingles / self adhering underlayment.

<u>Item #8</u> – Section 011100 Summary of Work, 1.3, E, Add to the scope of work, removal all un used pipes and roof curbs prior to the installation of the new roofing system. The district will assist with electrical and water disconnections.

<u>Item #9</u> – Section 011100 Summary of Work, 1.3, E, Add to the scope of work, at the swamp cooler located on building E sloped roof section install new 24 gauge galvanized sheet metal roof jack and sheet metal flashing.

End of addendum #1

Addendum #1 must be signed, dated and returned with bid to confirm receipt and acknowledgment

Signed	 	 	
Date	 	 	
Print Name			

MADERA UNIFIED SCHOOL DISTRICT

1902 Howard Road, Madera, California 93637 (559) 675-4500 FAX: (559) 675-1186 www.madera.k12.ca.us



Board of Trustees:

Ruben Mendoza, President Brent Fernandes, Clerk **Trustees:**

Ricardo Arredondo, Joetta Fleak, Ed McIntyre, Lucy Salazar, Ray G. Seibert

Superintendent: Todd Lile