



**MADERA UNIFIED
SCHOOL DISTRICT**
1902 Howard Road
Madera CA 93637
(559) 675-4500
(559) 675-1186 Fax
www.madera.k12.ca.us

Board of Trustees:

President:
Ed McIntyre

Clerk:
Lucy Salazar

Trustees:
Nadeem Ahmad
Isreal Cortez
Joetta Fleck
Ruben Mendoza
Lucy Salazar
Ray G. Seibert

SUPERINTENDENT:
Todd Lile

February 4, 2022

**Addendum No.1 Bid No.012022- Roof Coating Projects at
Multiple School Sites**

NOTICE TO ALL VENDORS:

This Addendum is attached to and made a part of the above-entitled specifications for Madera Unified School

District for **Bid No012022- Roof Coating Projects at Multiple
School Sites** with a due date of February 10, 2022 @ 2:00 pm

All changes and/or clarifications will appear in bold type and deletions will be struck out within a sentence.

Questions/Clarifications:

Questions:

1. Can you provide the engineer's estimate for Bid No.012022-
Roof Coating Projects at Multiple School Sites? **\$150,000.00**

Clarifications:

- Add to Section 01 11 00 Summary of Work 1.3, 3; At the Madera HS Library Add 20' of 4" x 4" galvanized 90 degree edge metal as a water diverter in place of the existing water diverter. Angle both diverters to push water to the outside edge. Install in the top coat with polyester reinforcement.
- Add to Section 01 11 00 Summary of Work 1.3, 3; At the Madera HS Library install 6" wide uni bond tape around the HVAC curb counterflashing as discussed at the pre bid meeting.
- Add to Section 01 11 00 Summary of Work 1.3, 3; At the Madera HS Library & Easton Arcola remove all existing loose coating from the roofing system prior to pressure washing the existing roof.
- Add to Section 01 11 00 Summary of Work 1.3, 3; At the Madera HS Library remove the existing ladder safety posts at the roof level, patch the roof to match the existing height. Install a new Bilco or equal Ladder Up Safety Post to the existing ladder.
- Add to Section 01 11 00 Summary of Work 1.3, 3; At the Madera HS Library & Easton Arcola install all new wood blocking and attach to all conduit, gas lines, condensate lines, etc. with a cap sheet slip sheet under the wood block.
- Add to Section 01 11 00 Summary of Work 1.3, 3; At Easton Arcola clean all gutters as part of the pressure washing and preparation for restoration.

- Add to Section 01 11 00 Summary of Work 1.3, 3; At Easton Arcola remove and dispose of all dormer vents. Install a new low profile dormer vent similar to Award Metals Low Profile Dormer and patch them back into the roof system per the manufacturer's instructions.

Allowance Added: See attached updated Bid Form

Signature_____

Date_____