

Madera Unified School District

1902 Howard Road, Madera, CA 93637
559.675.4500
Fax: 559.675.1186
www.madera.k12.ca.us

February 26, 2024

Addendum No. 1 RFP No.021324-Audio-Visual System-Rebid

NOTICE TO ALL VENDORS:

This addendum is attached to and made a part of the above-entitled specifications for Madera Unified School District for RFP. No 021324-Audio-Visual System-Rebid with a due date of **March 01, 2024 @ 10:00:00 am**

All changes and/or clarifications will appear in bold type and deletions will be struck out within a sentence.

Questions:

1. What are the quantities of "TZ-GT 1424x4 spigot (or equal)" requested? **23 10'**
2. Can we assume 2 complete sets of hoists, since listed below "Thought is to leave 1 set of motors and cables permanently in 2 of the venues"? **yes**
3. (26) 25ft. Steel cable? Should it be 5ft steel? **no 25'**
4. Should non-specialty wrenches, hammers, etc be included with the requested "[...] nuts, bolts etc..." in the Lighting/Rigging Part? **everything needed to assemble the systems**
5. 12 Ultimate Support are listed without a model. There are 24 mics requested. Should we list a tripod leg version since the round base version is specified in the next line item? **yes**
6. What is Madera's expected project schedule? Installation / First Setup date? Completion date? Define or elaborate on "first setup"? **Portable first sup date, not install. 90 days from day of contract awarded, with the understanding that some items may come later and need may need rentals to fill gaps**
7. Define or elaborate on "move between venues... 2 of the venues" noted on page 5
• Include facility names and addresses. **Yes, training, programing and set up needed.**
8. Drawing shows 2x "Power distro 1 of 2" are these existing or part of the bid? **(2) Two 48-way Distros needed, Matilde Torres High School and Madera High School. Possibility of other schools in the District**


Todd Lile
Superintendent

Board of Trustees
Lucy Salazar, President

Ruben Mendoza, Clerk
Nadeem Ahmad

Israel Cortes
Gladys A. Diebert

Joetta Fleak
Ray G. Seibert



Madera Unified School District

1902 Howard Road, Madera, CA 93637
559.675.4500
Fax: 559.675.1186
www.madera.k12.ca.us

9. Has an Architectural / Structural Engineer been established from Madera Unified School District for approving Rigging points to structural elements? Are vendors required to facilitate Structural Engineering Drawings and Approvals within Bid? **No District will provide**
10. What is ceiling height? **50' Chain for the motors will facilitate all use cases**
11. Is the VWX accurate for heights and trims? **No**
12. Drawings show a total of 23 10' truss sections RFP calls out 20? **23 Truss are needed**
13. Help clarify, "2 complete sets of motors and cable 13 1-ton and 2x 1/2 ton motors? • (2) 1/2-ton motors • Is this defined as (26) 1-ton Motors / (4) 1/2-ton Motors? **Yes, 13 1-ton and 2 half tone motors**
14. Drawings show a spare 1 ton, Include 1 additional with case? **Yes, a spare**
15. Is an 8 way enough as there would be possibly 9 motors moving for the front line? **Yes**
16. Are there existing rigging points in the ceiling for the motors? **Beams in the ceiling**
17. Motors or chain attach to ceiling, motor cables run in ceiling over to control land? **Yes**
18. Do local laws allow for permanent temporary motors and cables, or do cables need to be installed in conduit? **Temp is allowed**
19. What is ceiling height? **Varies from venue to venue, 50' chair is fine**
20. Motors will need yearly service by trained professionals, that may require removing them from the installed location. **Noted**


Todd Lile
Superintendent

Board of Trustees
Lucy Salazar, President

Ruben Mendoza, Clerk
Nadeem Ahmad

Israel Cortes
Gladys A. Diebert

Joetta Fleak
Ray G. Seibert



Madera Unified School District

1902 Howard Road, Madera, CA 93637
559.675.4500
Fax: 559.675.1186
www.madera.k12.ca.us

21. Is there a loading dock and clear path into the venue to unload these loaded sections of truss into the site? **Sites are multiple, but clear paths are available, most likely coming off a trailer lift**
22. 48 Dimming channels? + power for all LED/moving fixtures? **No dimming required, 2 48-way distros**
23. Is the intention for the fixtures to be delivered already loaded and cabled in the Tyler GT truss? **Would need to have them prebuilt and flashed prior to delivery.**
24. Do you want one lighting distro or two? The RFP calls for 1 but there are 2 locations on the drawing? **2-48 way's**
25. To my knowledge Tyler doesn't make a variable angle hinge that is load bearing, Can we provide a 45degree gate instead? **Spanset each truss for the point hinge points**
26. Are we only providing rigging hardware for the motor to truss attachment and the safety lock off hardware called out? What about top rigging attachment to building? **Yes, safety motor and beam clamp at top**
27. Will there be a qualified rigger onsite for installation? Will they have the lifts required / needed to complete the work? **Yes**
28. Has the engineering been done to verify the loads can be suspended as intended? **Yes**
29. The Ayrton Bora S is a 40,000-lumen arena type fixture. Probably overkill for this application as it's really intended for longer throws. Can we switch this to an Ayrton Revelle or Diablo which is better suited for shorter throws? **Prefer to keep Bora for beam spread and day time shows**
30. Clay Paky Styles requires laser certification training and operator and has very specific limitations on use. Would an Elation Radius or similar type fixture that


Todd Lile
Superintendent

Board of Trustees
Lucy Salazar, President

Ruben Mendoza, Clerk
Nadeem Ahmad

Israel Cortes
Gladys A. Diebert

Joetta Fleak
Ray G. Seibert



Madera Unified School District

1902 Howard Road, Madera, CA 93637
559.675.4500
Fax: 559.675.1186
www.madera.k12.ca.us

doesn't require an FAA license to operate be a better option? **Skilos is variance free, but would be willing to look to Elation**

31. Is there an equipment rack onsite to house node / opto splitter if needed or should we include a rolling data rack for that? **Non-rolling rack needed SKB/Gator or equal 4u-8u rack to set atop distro.**

32. The GrandMA3 Compact and XT currently has a ship date well into 2025. If you want to stay in the MA line of consoles it will most likely be a long lead time item. • Will Rental or used console might be needed for short term coverage? **Used console is fine.**

33. What are the Gamma lifts intended for? **Flying Truss in certain locations**

34. Tie on top of drape or hidden behind? **On Top**

35. Elaborate on Fullness? 50%? **'50% fullness Skylos NV(Non-Variance) the 1st and only laser fixture on the entertainment lighting market except from FDA CDRH variance**

36. Where is it rigged to? Dedicated pipe? **Tyler GT Truss back cord**

37. Remote Antennas for Wireless? **2x Shure LPDA Style or Equivalent**

38. More detail online item "12 Ultimate Support"-**Mic Stands**

39. Meyer MSL-4 is a Legacy product – Please specify current model? **MSL-4's**

40. Needs cable package for microphones+ possible snakes from audio control BOH to stage.. **(Cable package is at discretion of the bidder)**

41. Where does power come from? Existing distro?? **2 x48 Way Distro-1 for LX and 1 for AUD/VID**

42. Only one 16ch Rio box spec'd but 24 microphones spec'd. Replace with a Rio3224? **Replace with Rio3224**


Todd Lile
Superintendent

Board of Trustees
Lucy Salazar, President

Ruben Mendoza, Clerk
Nadeem Ahmad

Israel Cortes
Gladys A. Diebert

Joetta Fleak
Ray G. Seibert



Madera Unified School District

1902 Howard Road, Madera, CA 93637
559.675.4500
Fax: 559.675.1186
www.madera.k12.ca.us

43. Dedicated Dante switch is absent from list, prepared manufacture/model? **Netgear M4250 or Equivalent managed switch**
44. 2 Options for "YESTECH MG7S 3.9m" 4000-4200 nits and 5500-6000 nits • What are your preferred nits intended for this project? **4K Nit is acceptable**
45. Where does video processing live? **8U Rack needed for Processing**
46. How will video be switched to the Video walls? **Laptop is switching content**
47. Does LED get powered through equipment in lighting or should it have its own distro? Looking at approx. 40-150A single phase 110v? **Dedicated 48 way Distro for AUD/VID**

Signature: _____

Date: _____

Todd Lile
Superintendent

Board of Trustees
Lucy Salazar, President

Ruben Mendoza, Clerk
Nadeem Ahmad

Israel Cortes
Gladys A. Diebert

Joetta Fleak
Ray G. Seibert