

May 12, 2020

Addendum No.2
Bid No.040720-Asphalt Resurface & Repair Projects at Various School Sites

NOTICE TO ALL VENDORS:

This Addendum is attached to and made a part of the above-entitled specifications for Madera Unified School District for Bid No.040720-Asphalt Resurface & Repair Projects at Various School Site, with a due date of May ~~6~~, **19**, 2020 @ 10:01 a.m.

All changes and/or clarifications will appear in bold type and deletions will be struck out within a sentence.
Questions/Clarifications:

Clarifications:

John Adams:


1. Remove and replace with 3" asphalt over 6" compacted native subgrade base (parking lot spec).
2. Remove valley gutter and grade asphalt out to the field.
3. After the removal of asphalt pavement, the district will need to install new water mains shut off valves to each building and replace the valve boxes before new asphalt is installed.

Martin Luther King:

1. Remove and replace with 3" asphalt over 6" compacted native subgrade base (parking lot spec).

La Vina:

1. Install a 3'x435' valley gutter.
2. At the north end of the valley-gutter, install an F08 Curb, valve box 8" I.D. x 12" with V01-71c cast iron grate lid for pump purposes.
3. Bring ADA parking stalls up to code (moving over two stalls to the north).
4. Reinstall existing wheel stops unless they are broken replace with new ones.
5. Section A. 3" asphalt over 6" compacted subgrade base (parking lot spec).
6. Section B. 4" asphalt over 6" compacted subgrade base (bus lane spec).



Questions:

1. Please confirm we do NOT need to seal coat sites getting full asphalt remove and replace? **Yes, confirmed.**
2. Do we need an Encroachment Permit for the work at La Vina? **Yes**
3. Will water be available at each of the school sites? **Yes**
4. Please confirm if we would removing the concrete v-gutter at John Adams and if so the new grading specs. **No, do not remove the v-gutter**
5. Please confirm if we would be adding a new concrete v-gutter at La Vina and if so the specs for that. **No v-gutter will be installed as part of contract.**
6. Per addendum no. 1, The District encourages mailed or emailed bid packets. If we decide to email the bid packet, will a scanned bid bond along with our packet be acceptable? **–Yes, the awarded vendor will be required to turn in all original paperwork upon award.**
7. The General Conditions call for builder's risk insurance on an "all risk" basis, however, since this is an asphalt project with no buildings involved, may we exclude earthquake and flood coverage from the builder's risk policy? **No, we need all insurance listed.**

Date_____

Signature_____