

MADERA UNIFIED SCHOOL DISTRICT 1902 Howard Road Madera CA 93637 (559) 675-4500 (559) 675-1186 Fax www.madera.k12.ca.us

Board of Trustees: <u>President</u>: Ed McIntyre

<u>Clerk</u>: Lucy Salazar

<u>Trustees</u>: Nadeem Ahmad Isreal Cortez Joetta Fleck Ruben Mendoza Lucy Salazar Ray G. Seibert

SUPERINTENDENT: Todd Lile

February 1, 2022

Addendum No.2 Bid No.010522-Thomas Jefferson MS HVAC Project

NOTICE TO ALL VENDORS:

This Addendum is attached to and made a part of the above-entitled specifications for Madera Unified School District for **Bid No. 010522-Thomas Jefferson MS HVAC Project** with a due date of February 2 9, 2022 @ 10:01 am All changes and/or clarifications will appear in bold type and deletions will be struck out within a sentence. Questions/Clarifications:

Updated Bid Turn In-Due date of February 9, 2022 @ 10:01 am.

Responses to RFI" s

DRAWINGS:

Item 2-01 – Sheet M0.2: Air Distribution Schedule: Symbol G shall be changed to the following: Fixed louvered face diffuser, aluminum construction. Titus model TDC-1.

Item 2-02 – Sheet M2.1: A. Symbol G diffusers shall be changed to 48"x12"-4 size and the 36"x9" duct drops thru roof in keynote 4 shall be revised to 48"x9" with transition at ceiling grille.

Pre-Bid Questions and Clarifications

- **1. Is the existing gym floor concrete or wood framing?** Response: Concrete
- **2.** Is there a specific method for gym floor protection required? Response: No, the contractor controls its means and methods
- Have the ceiling tiles and glue in the wrestling room been tested for asbestos?
 Response: No. The District will have them surveyed. The District will be responsible for abatement if asbestos is found.
- **4.** What is the ceiling finish material in the gym? Response: The ceiling appears to be acoustic gyp board.

5. The roofing detail (Sheet E3.2 / Detail 2) illustrates laying the B-22 channel directly on the roofing. On the job walk, I noticed that the existing conditions were utilizing roof blocks. Please advise. Response: The use of Cooper B-Line DB Series roof supports is acceptable for intermediate supports. Supports at equipment, change of direction, and every 20'-0" shall be per approved plans

Updated Bid Form (see attached)

An allowance fund of \$25,000.00 has been added to the project.

Signature_____

Date_____