



May 13, 2020

Addendum No.5  
Bid No.040720-Asphalt Resurface & Repair Projects at Various School Sites

**NOTICE TO ALL VENDORS:**

This Addendum is attached to and made a part of the above-entitled specifications for Madera Unified School District for Bid No.040720-Asphalt Resurface & Repair Projects at Various School Site, with a due date of May ~~6~~, **19**, 2020 @ 10:01 a.m.

All changes and/or clarifications will appear in bold type and deletions will be struck out within a sentence.  
Questions/Clarifications:

**Questions/Clarification:**

1. I see that we will no longer have to install a valley gutter.  
Would this still be part of the bid, are you still wanting the valve box at the end of the pavement where they have to pump out water? Please advise  
"At the north end of the valley-gutter, install an F08 Curb, valve box 8" I.D. x 12" with V01-71c cast iron grate lid for pump purposes" **Deleted from scope of work**
2. Under addendum no. 2, "Clarifications" La Vina, item number 6, says to install 4" asphalt over 6" compacted subgrade base, (bus lane spec.), however, under the "Asphalt Resurfacing Repair Specification, states that the bus lane shall be constructed with the installation of 4" of hot asphalt and 6" over base (unlike the parking lots and playground areas, as they call for 6" of compacted native subgrade base). We were under the impression that you meant class II aggregate base. Please clarify if you will require 6 inches of class II AB or not? **4" of (new) hot asphalt in two 2" lifts over 6"of compacted native subgrade base**

Date\_\_\_\_\_

Signature\_\_\_\_\_