

Addendum No. 1  
Roofing Projects at Various School Sites  
Bid No. 012317

**NOTICE TO ALL VENDORS:**

This Addendum is attached to and made a part of the above entitled specifications for Madera Unified School District with a BID due date of March 2<sup>nd</sup>, 2017

Bid Section No. 1 - 2:00 pm  
Bid Section No. 2 - 2:30 pm  
Bid Section No. 3 - 3:00 pm

All changes and/or clarifications will appear in bold type and deletions will be struck out within a sentence.

**MADISON ELEMENTARY SCHOOL**


1. Section 01 11 00 Summary of Work 1.3, E, Add to the scope of work. Install new 4" x 4" minimum 24 gauge galvanized sheet metal 1/4" low rise gravel stop with 22 gauge cleat at all reroofing sections only. The existing fascia cover is to remain in place. Prepare, prime, and paint the new sheet metal and the existing fascia cover per the district approved color.
2. Section 01 11 00 Summary of Work 1.3, E, Add to the scope of work. Install new 24 gauge galvanized sheet metal flashing at all low window frames of the reroofing sections only. Install butyl tape behind the flashing and install tuff stuff urethane sealant.
3. Section 01 11 00 Summary of Work 1.3, E, Add to the scope of work. Install new pipe support blocking and protection pads at all roof sections "reroofing and restoration". Existing Uni Strut is to remain in place. Existing rubber blocks in good condition are also to remain in place.
4. Section 01 11 00 Summary of Work 1.3, E, Add to the scope of work. Install 1/4" per foot tapered insulation at the three roof sections on the lower canopies as discussed at the pre bid meeting.
5. **Clarification** - Bid Section No.1 Updated 07 52 00 spec section was only updated to turn off the edit notes for clarity. The original Bid Section No. 1 documents apply to the project and must be reviewed for other spec sections.

**MHS FIELD HOUSE**

1. Section 01 11 00 Summary of Work 1.3, E, Scope change, new gutter and downspout installation in lieu of fabricating scuppers to match the existing layout. Remove the existing wood nailers at the eve edge. Install new 24 gauge galvanized 6" x 8" gutter with soldered joints. Install new wire screen protection at the downspout drops. Install new 4" x 4" minimum 24 gauge galvanized sheet metal 1/4" low rise gravel stop. Install two (2) new schedule 40 round downspouts with welded mounting tabs and a 45 degree turn out at the bottom edge. Prepare, prime, and paint the new sheet metal and downspouts with a district approved color.

**SIERRA VISTA ELEMENTARY SCHOOL**

1. Section 01 11 00 Summary of Work 1.3, E, Add to the scope of work. Provide and install drain baskets to all roof drains.
2. **Clarification** - Section 01 11 00 Summary of Work, 1.3, E, Buildings C & J are to be removed from the scope of work and will not be part of this project.



3. **Clarification** - Bid Section No.3 Updated 07 52 00 spec section was only updated to turn off the edit notes for clarity. The original Bid Section No. 3 documents apply to the project and must be reviewed for other spec sections.
4. Section 01 11 00 Summary of Work 1.3, D, 2. Complete removal and replacement of roof section A is required. Install a minimum of 1/4" tapered roof insulation over the entire roof, all details will need to be configured to accommodate the tapered insulation.
5. Section 01 11 00 Summary of Work 1.3, D, 2. Change the amount and type of dryrot replacement included in the bid to 100 lineal feet of roof decking and 100 lineal feet of fascia board to match existing. All wood replacement is to be painted to match existing.

Addendum must be signed, dated and returned with bid to confirm receipt and acknowledgement.

Signed:\_\_\_\_\_

Date:\_\_\_\_\_

Print Name:\_\_\_\_\_