# **PROJECT MANUAL**

**Technical Specifications** 

for

Bid No.012022-Roof Coating Projects at Multiple School Sites



Madera Unified School District 1902 Howard Road Madera, CA 93637

# SECTION 01110

#### SUMMARY OF WORK

## PART 1 — GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including the Conditions of the Contract and Division 01 Specification Sections apply to this Section.

#### 1.2 SUMMARY

- A. Section includes roofing restoration of the specified existing roofing systems, coping, insulation, flashings, and removal of all construction related debris. Installation of a new restoration system as specified with all applicable details for a complete watertight warrantied roofing assembly per the manufacturers instructions.
- B. Materials specified in section 01 64 00 Owner Furnished Contractor Installed (O.F.C.I.) will be the responsibility of the contractor to receive, store, protect, and maintain in good condition throughout the course of the project.
- C. Related Work Specified Elsewhere:
- 1. Section 01 Owner Furnished Contractor Installed
- 2. Section 06 Rough Carpentry
- 3. Section 07: Roofing Restoration
- 4. Section 07: Sheet Metal Flashing and Trim

#### 1.3 WORK COVERED BY CONTRACT DOCUMENTS

- A. Project Identification: Bid No.012022-Roof Coating Projects at Multiple School Sites
- B. Project Locations:
  - A. Easton Arcola Elementary School 29551 Ave 8. Madera, CA 93638
  - B. Madera High School 100 S. L St. Madera, CA 93638
- C. Owner: Madera Unified School District 1205 S. Madera Ave. Madera, CA 93637
- D. General scope of work but not limited to;

#### 1. Easton Arcola Elementary School & Madera High School Library:

- 2. Preparation of existing roof system for restoration.
- 3. Pressure wash existing roofing system, duct work, and gutter systems allow to dry for 24 hours or until it is completely dry and ready to accept the new roof coating system.
- 4. Cut the existing roofing system back from gravel stop edge 2", scrape all loose asphalt and debris for a clean surface. Prime the metal and 6" back onto the existing roof surface with Garla Prime VOC allow to completely dry. Install one layer of Flashing Bond mastic, apply one layer of Garmesh 6" reinforcement, apply one more layer of Flashing Bond mastic, fully embed roofing granules into fresh mastic, allow to cure prior to the base coat / top coat application.
- 5. Three course all base flashing laps at roof areas with parapet walls with one layer of Flashing Bond mastic, one layer of 6" Garmesh, one layer of Flashing Bond mastic, and embed

roofing granules into the fresh mastic, allow to cure prior to application of the base coat / top coat.

- 6. Repair all loose membrane, buckles, blisters, etc. at edge flashing, base flashing, and through field along with all details as needed for a complete prepared roof surface.
- 7. Install new drain baskets at all roof drain locations. Check and tighten if needed all drain bolts.
- 8. Cut open, mechanically attach, and three course all blisters and repair all details per specification as needed for a complete prepared roof surface.
- 9. Install Garla-Block Primer at all roof areas at a rate of 1/2 gallon per square.
- 10. Install Pyramic Acrylic Coating per specification at a total rate (3) gallons per square in two coats at all built up roof areas, vents, duct work, and sheet metal items. Back roll the base coat and the top coat as needed to promote full adhesion, clean appearance, complete coverage, and proper mil thickness. Top coat is to be completed in a cross hatch pattern. Additional coats may be needed for the proper coverage and appearance.

#### 1.4 WORK COMPLETED BY THE DISTRICT

A. No work will be completed by the district.

#### 1.5 TYPE OF CONTRACT

- A. Work will be completed under a single prime contract.
- B. Owner Supplied Contractor Installed (O.F.C.I.). Materials will be clearly noted at the back of each specification section as to what is being supplied by the owner. All O.F.C.I. materials are to be installed as part of this contract by the contractor. All other materials needed to complete this scope of work and are not specifically listed in the owner supplied materials section will be the responsibility of the contractor to supply and install.

#### 1.6 USE OF PREMISES

- A. General: Contractor will have limited use of premises for construction operations.
- B. Use of site: Limit use of premises to work areas required. Do not disturb portions of the project site beyond areas in which the work is indicated.
- C. The building interior is off limits to the contractor. All access shall be from the exterior.
- D. The point of exterior access must be approved by the owner.
- E. Entrances: Keep all entrances serving the building clear and available to the owner, owner's employees, and emergency vehicles.
- F. Use of existing building: Maintain existing building in a weather tight condition throughout the construction period. Repair damage caused by construction operations. Protect building and occupants during construction.
- G. Vehicle Parking: Contractor parking is available on site and will need to be approved by the owner.
- H. Assume full responsibility for protection and safekeeping of materials stored on premises. Coordinate the location of materials and equipment to be stored on premises. Provide barricades, barriers, and enclosures as required to ensure safety.

#### 1.7 OWNERS OCCUPANCY REQUIREMENTS

A. The owner will occupy the building during the entire construction phase. Cooperate with the owner during construction operations to minimize owner conflicts and facilitate owner usage. Perform the work as to not interfere with owners operations.

B. A minimum of 72 hours notice is needed for all activities that will affect the owners operations.

# 1.8 WORK RESTRICTIONS

- A. On site work hours: Work shall generally be performed from the hours of 7:00 am 5:00 pm Monday through Friday except as otherwise indicated or approved by the owner.
- B. Weekend hours, early morning hours, utility shut down, and noisy activity requires owner's authorization a minimum of 72 hours in advance.

#### 1.9 UNIT PRICES

- A. The following unit prices will be used to add or deduct from the total contract amount.
  - 1. Replacement of wood roof decking and fascia board.

#### 10. SCHEDULE OF ALTERNATES

A. None

#### 1.11 PROJECT CONDITIONS

- A. Proceed with roofing work only when existing and forecasted weather conditions will permit a unit of work to be installed in accordance with manufacturer's recommendations and warranty requirements.
- B. Do not apply roofing insulation or membrane to damp deck surface.
- C. Do not expose materials subject to water or solar damage in quantities greater than can be weatherproofed during same day.

## 1.12 SEQUENCING AND SCHEDULING

- A. Sequence installation of roofing with related units of work specified in other sections to ensure that roof assemblies, including roof accessories, flashing, trim and joint sealers, are protected against damage from effects of weather, corrosion and adjacent construction activity.
- B. Complete all roofing field assembly work each day. Phased construction will not be accepted. Phased construction refers to the application of the roof insulation board, ply sheet membrane, and cap sheet membrane installed in the same day.
- C. Due to the cure time needed for the roofing system prior to the acrylic coating scheduling of work past the completion date of <u>August 5, 2022</u> will need to be reviewed and agreed upon by all parties. Work can only be completed during weekends or off hours past the project completion date unless otherwise reviewed and approved by the district. All coating work and 100% project completion shall be no later than 9/30/2022. Including punch list and final inspection. All days after 9/30/22 will have liquidated damages applied. specifically approved by the Owner.

#### 1.13 PROJECT TIMELINE

- A. Project Start: June 6, 2022
- B. Project Completion: August 5, 2022

END OF SECTION 01 11 00 – SUMMARY OF WORK





#### SECTION 01 30 00 SUBMITTALS

#### PART 1 – GENERAL

#### 1.01 RELATED DOCUMENTS

- A. Contract General Conditions.
- B. See also contract general conditions for additional requirements especially those regarding requests for ALTERNATIVES OR EQUALS and for SUBSTITUTIONS.

#### 1.02 SUMMARY

- A. This Section specifies administrative and procedural requirements for submittals required for performance of the Work, including:
  - 1. Contractor's construction schedule
  - 2. Submittal schedule
  - 3. Shop Drawings
  - 4. Product Data
  - 5. Samples.
- B. Administrative Submittals: Refer to other Division1 Sections and other Contract Documents for requirements for administrative submittals. Such submittals include, but are not limited to:
  - 1. Permits
  - 2. Applications for payment
  - 3. Performance and payment bonds
  - 4. Insurance certificates
  - 5. List of Subcontractors.

#### 1.03 SUBMITTAL PROCEDURES

- A. Coordination: Coordinate preparation and processing of submittals with performance of construction activities. Transmit each submittal sufficiently in advance of performance of related construction activities to avoid delay.
  - 1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals and related activities that require sequential activity.
  - 2. Coordinate transmittal of different types of submittals for related elements of the Work so processing will not be delayed by the need to review submittals concurrently for coordination.
    - a. The Architect shall return without action any submittals requiring coordination with other submittals until related submittals are coordinated.
  - 3. Processing: Allow sufficient review time so that installation will not be delayed as a result of the time required to process submittals, including time for resubmittals.
    - a. See General Conditions and Supplementary General Conditions for additional requirements.
    - b. If an intermediate submittal is necessary, process the same as the initial submittal.
    - c. No extension of Contract Time will be authorized because of failure to transmit submittals to the Architect sufficiently in advance of the Work to permit processing.

- B. Submittal Preparation: Place a permanent label or title block on each submittal for identification. Indicate the name of the entity that prepared each submittal on the label or title block.
  - 1. Provide a space approximately 4" x 5" on the label or beside the title block on Shop Drawings to record the Contractor's review and approval markings and the action taken.
  - 2. Include the following information on the label for processing and recording action taken:
    - a. Project name
    - b. Date
    - c. Name and address of Architect
    - d. Name and address of Contractor
    - e. Name and address of subcontractor
    - f. Name and address of supplier
    - g. Name of manufacturer
    - h. Number and title of appropriate Specification Section
    - i. Drawing number and detail references, as appropriate.
- C. Submittal Transmittal: Package each submittal appropriately for transmittal and handling. Transmit each submittal from Contractor to Architect using a transmittal form. Submittals received from sources other than the Contractor will be returned without action.

On the transmittal Record relevant information and requests for data. On the form, or separate sheet, record deviations from Contract Document requirements, including minor variations and limitations. Include Contractor's certification that information complies with Contract Document requirements.

#### 1.05 SHOP DRAWINGS

- A. Submit newly prepared information, drawn to accurate scale. Highlight, encircle, or otherwise indicate deviations from the Contract Documents. Do not reproduce Contract Documents or copy standard information as the basis of Shop Drawings. Standard information prepared without specific reference to the Project is not considered Shop Drawings.
- B. Shop Drawings include fabrication and installation drawings, setting diagrams, schedules, patterns, templates and similar drawings. Include the following information:

Dimensions Identification of products and materials included Compliance with specified standards Notation of coordination requirements Notation of dimensions established by field measurement.

- C. Sheet Size: Except for templates, patterns and similar full size Drawings, submit Shop Drawings on sheets at least 81/2" x 11" but no larger than 30" x 42".
- D. Submittals: Submit one correctable translucent reproducible print and six (6) blue or blackline print for the Architect's review; the reproducible and one print will be returned.

Do not use Shop Drawings without an appropriate final stamp indicating action taken in connection with construction.

#### 1.06 PRODUCT DATA

- A. Collect Product Data into a single submittal for each element of construction or system. Product Data includes printed information such as manufacturer's installation instructions, catalog cuts, standard color charts, roughingin diagrams and templates, standard wiring diagrams and performance curves. Where Product Data must be specially prepared because standard printed data is not suitable for use, submit as "Shop Drawings."
  - Mark each copy to show applicable choices and options. Where printed Product Data includes information on several products, some of which are not required, mark copies to indicate the applicable information. Include the following information:

Manufacturer's printed recommendations,

Compliance with recognized trade association standards,

- Compliance with recognized testing agency standards,
- Application of testing agency labels and seals,
- Notation of dimensions verified by field measurement,
- Notation of coordination requirements.
- 2. Do not submit Product Data until compliance with requirements of the Contract Documents has been confirmed.
- B. Submittals: Submit a minimum of six (6) copies of each required submittal as well as additional copies as required by the Architect, (the actual number of submittals and distribution required shall be determined by the Trustees Representative at the Preconstruction Conference). The Architect will return two sets marked with action taken and corrections or modifications required.
- C. Distribution: Furnish copies of final submittal to installers, subcontractors, suppliers, manufacturers, fabricators, and others required for performance of construction activities.
  - 1. Do not proceed with installation until an applicable copy of Product Data applicable is in the installer's possession.
  - 2. Do not permit use of unmarked copies of Product Data in connection with construction.

#### 1.07 SAMPLES

- A. Submit full-size, fully fabricated Samples cured and finished as specified and physically identical with the material or product proposed. Samples include partial sections of manufactured or fabricated components, cuts or containers of materials, color range sets, and swatches showing color, texture and pattern.
  - Mount, display, or package Samples in the manner specified to facilitate review of qualities indicated. Prepare Samples to include the following: Generic description of the Sample Sample source Product name or name of manufacturer Compliance with recognized standards Availability and delivery time.
  - 2. Submit Samples for review of kind, color, pattern, and texture, for a final check of these characteristics with other elements, and for a comparison of these characteristics between the final submittal and the actual component as delivered and installed.
- B. Preliminary submittals: Where Samples are for selection of color, pattern, texture or similar characteristics from a range of standard choices, submit a full set of choices for

the material or product.

Preliminary submittals will be reviewed and returned with the Architect's mark indicating selection and other action.

C. Submittals: Except for Samples illustrating assembly details, workmanship, fabrication techniques, connections, operation and similar characteristics, submit 3 sets; one will be returned marked with the action taken.

Maintain sets of Samples, as returned, at the Project site, for quality comparisons throughout the course of construction.

D. Distribution of Samples: Prepare and distribute additional sets to subcontractors, manufacturers, fabricators, suppliers, installers, and others as required for performance of the Work.

Field Samples specified in individual Sections are special types of Samples. Field Samples are full-size examples erected on site to illustrate finishes, coatings, or finish materials and to establish the standard by which the Work will be judged.

#### 1.08 ARCHITECTS ACTION

A. Except for submittals for record, information or similar purposes, where action and return is required or requested, the Architect will review each submittal, mark to indicate action taken, and return promptly.

Compliance with specified characteristics is the Contractor's responsibility.

- B. Action Stamp: The Architect will stamp each submittal with a uniform, self-explanatory action stamp. The stamp will be appropriately marked, as follows, to indicate the action taken:
  - 1. Final Unrestricted Release: Where submittals are marked "Approved," that part of the Work covered by the submittal may proceed provided it complies with requirements of the Contract Documents; final acceptance will depend upon that compliance.
  - 2. Final-But-Restricted Release: When submittals are marked "Approved as Noted," that part of the Work covered by the submittal may proceed provided it complies with notations or corrections on the submittal and requirements of the Contract Documents; final acceptance will depend on that compliance.
  - 3. Returned for Resubmittal: When submittal is marked "Not Approved, Revise and Resubmit," do not proceed with that part of the Work covered by the submittal, including purchasing, fabrication, delivery, or other activity. Revise or prepare a new submittal in accordance with the notations; resubmit without delay. Repeat if necessary to obtain a different action mark.
    - a. Do not permit submittals marked "Not Approved, Revise and Resubmit" to be used at the Project site, or elsewhere where Work is in progress.
    - b. <u>Note:</u> Any work performed prior to receiving a FULLY APPROVED submittal shall be done at the contractors own risk and is subject to being replaced if any of the submittal requirements are not met.

# PART 2 – PRODUCTS NOT USED

PART 3 – EXECUTION NOT USED

END OF SECTION 01300

#### **SECTION 01 64 00**

# OWNER FURNISHED CONTRACTOR INSTALLED (O.F.C.I)

#### PART 1 - GENERAL

#### 1. SUMMARY

- A. DESCRIPTION: The Owner shall procure and provide certain products for installation as shown and specified per Contract Documents.
- B. RELATED WORK SPECIFIED ELSEWHERE:
  - 1. General: Products furnished and paid for by the Owner are described in the following technical sections and /or in the Drawings as O.F.C.I. materials.
  - 2. Note that this project includes the installation of owner-supplied materials as noted in this specification section only. All materials not specifically listed below will be the responsibility of the contractor to provide and install.

#### 2. DEFINITIONS

- A. GENERAL: The following are used to identify products as noted on the Drawings.
- B. OWNER FURNISHED CONTRACTOR INSTALLED (O.F.C.I.): Products or equipment furnished by the Owner for installation under this contract.
- C. OWNER FURNISHED OWNER INSTALLED (O.F.O.I.): Products or equipment to be provided and installed by the Owner, but requiring surfacing, backing, utility connections or other preparation under this contract, for proper installation.
- D. NOT IN CONTRACT (N.I.C.): Products or equipment to be provided and installed by Owner, not requiring surfacing, backing, utility connections or other preparation under this contract.

#### PART 2 - PRODUCTS

#### 1. PRODUCTS

- A. ROOFING MATERIAL FURNISHED BY OWNER (O.F.C.I.): District supplied material. Related specification sections include;
  - 1. Section 07 Roofing Restoration
  - 2. Section 07 Sheet Metal Flashing and Trim

#### B. MATERIAL LIST

1. The Owner will only supply the quantity listed in the owner supplied materials section of this specification below. All additional materials and accessories will be the full responsibility of the contractor to provide and install per the specification and project requirements.

OWNER FURNISHED CONTRACTOR INSTALLED 01 64 00 - 1

- 2. Any and all material or accessories required for the installation of the roof system in excess of the district provided material must be supplied and installed by the Contractor. It is up to the Contractor to determine the precise amount of material required for the completion of this project; and to provide excess material, as required. The cost to handle and break flashing metal from the District provided flat stock is contractor's responsibility.
- All required flashings as required per each specification section for plumbing, electrical, gas, etc. will be the Contractors responsibility to provide and install as well as to be included in the bid cost.
- 4. All materials not specifically included in the owner supplied materials section will be the responsibility of the contractor to provide and install in compliance with the respective specification section.
- 5. Freight charges of owner supplied materials will be the responsibility of the Owner.
- 6. Contractor must coordinate and take delivery of materials, count all materials and ensure it matches the list below, unload and properly locate materials at the job site, and properly protect, cover and store at job site.
- 7. Contractor must be able to provide certification in writing from roof system manufacturer that the contractor is approved to install the specified roof system and provide all warranty requirements of each respective specification section.
- 8. Materials specially provided by the owner:

| 5.00  | Stressply Plus FR Mineral, 75 sq ft per rl        |
|-------|---|
| 3.00  | Stressbase 80, 150 sq ft per rl                   |
| 10.00 | Uni Bond ST Tape 4" x 50'                         |
| 30.00 | Tuff Stuff Urethane Caulking 10.1 oz tube (White) |
| 15.00 | Garmesh 6" x 150'                                 |
| 3.00  | Garla-Prime VOC, 5 gallon pail                    |
| 45.00 | Flashing Bond Mastic, 5 gallon pail               |
| 22.00 | Pyramic Plus Lo Acrylic Coating, 55 gallon drum   |
| 3.00  | Weatherking Plus WC, 5 gallon Pail                |
| 3.00  | Standard Roofing Granules, 50 lb bag              |
| 30.00 | Garla Flex, 10 oz tube                            |
| 40.00 | Garla-Block Primer, 5 gallon pail                 |

#### PART 3 - EXECUTION

#### 1. OWNER'S RESPONSIBILITIES

A. SUBMITTALS: Arrange for and deliver necessary shop drawings, product data and samples to Contractor.

OWNER FURNISHED CONTRACTOR INSTALLED 01 64 00 - 2

#### B. DELIVERY:

- 1. General: Arrange and pay for product delivery to the site, in accordance with construction schedule.
- 2. Bill of Materials: Deliver supplier's documentation to Contractor.
- 3. Inspection: Inspect jointly with Contractor.
- 4. Claims: Submit for transportation damage and replacement of otherwise damaged, defective, or missing items.
- C. GUARANTEES: Arrange for manufacturer's warranties, bonds, service, inspections, as required.

#### 2. CONTRACTOR'S RESPONSIBILITIES

- A. SUBMITTALS: Review shop drawings, product data and samples and submit to Architect and/ or Owner with notification of any discrepancies or problems anticipated in use of product.
- B. DELIVERY:
  - 1. General: Designate delivery date for each product in Progress Schedule.
  - 2. Receiving: Receive and unload products at site. Handle products at the site, including un-crating, protection, and storage.
  - 3. Inspection: Promptly inspect products jointly with Owner; record shortages, damaged or defective items. Shortages and/or damage must be noted at the time of delivery by the contractor no claims may be made after the fact.
  - 4. Storage: Protect products from damage or exposure to elements per the manufactures requirements.

#### C. INSTALLATION:

- 1. General: Assemble, install, connect, adjust and finish products, as stipulated in the respective section of Specifications.
- 2. Repair and Replacement: Items damaged during handling and installation.
- 3. Install all O.F.C.I. products per the specifications and manufacturer instructions.
- 4. All products not supplied by the owner are the responsibility of the contractor to supply and install per manufacturers instructions.

#### END OF SECTION

OWNER FURNISHED CONTRACTOR INSTALLED 01 64 00 - 3

#### SECTION 06 10 00 ROUGH CARPENTRY

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and other Division-1 Specification sections, apply to work of this section.
- B. Related work specified elsewhere:
  - 1. Division 01: Summary of Work
  - 2. Division 07: Roofing Restoration
  - 3. Division 07: Sheet Metal Flashing and Trim

#### 1.2 SUMMARY:

A. This portion of the specification sets forth the general requirements, including the quality and type of materials required for the installation of all pressure treated and non pressure treated lumber used for wood curbs, nailing strips, miscellaneous blocking material, unexposed fillers, fascia, edging strips, deck replacement, etc

#### 1.3 STORAGE:

A. All material specified herein shall be stored (after delivery to the site) so that it will be fully protected from damage and weather, and shall be stacked to prevent damage. All lumber shall be fully protected to maintain the original required moisture content as specified in item titled "Moisture Content".

#### 1.4 OTHER REQUIREMENTS:

A. Dimensions indicated on the drawings are nominal dimensions (except where details show actual sizes) and shall be subject to the standard reductions required for surfacing or tolerances permitted by the grading rules. Unless otherwise indicated on drawings, all material shall be S4S (surfaced four sides).

#### 1.5 **PROTECTION**:

A. All finished work shall be adequately protected against damage from any source.

#### 1.6 COORDINATION:

A. Carpenters shall coordinate their work with that of the other trades so that progress continues without interruption.

#### PART 2 - PRODUCTS

#### 2.1 WOOD - FRAMING AND CURBS:

A. GRADING RULES, GRADES, AND SPECIES

Lumber: Southern Pine, yellow pine, Douglas fir, spruce, ponderosa pine, larch 1. or Hemlock and shall meet the following minimum grade requirement of construction standard (75% #1 and 25% #2); free from warping and visible decay. Lumber shall be graded according to the standard grading rules of the Southern Pine Inspection Bureau, the West Coast Lumber Inspection Bureau, or the Western Wood Products Association.

#### **MOISTURE CONTENT** В.

All lumber shall be air-dried or kiln-dried before treatment, so that the moisture 1. content is not more than 19%. After treatment, it shall be kiln-dried at temperatures not exceeding 160 degrees F. (71 degrees C) so that the moisture content is not more than 19% at time of shipment

#### С. **DECAY-RESISTANT TREATMENT:**

- 1. Lumber in contact with roofing or acting as fascias, and all other exterior lumber, shall be pressure-treated with a waterborne preservative in accordance with AWPA Specification P5. Creosote and oil-borne preservatives are not acceptable.
- Treating processes, material conditions, plant equipment, and other pertinent 2. requirements shall conform to AWPA Specifications C1 and C2 for specific kind of lumber and type of preservative to be used. Retention shall be as required for intended use.
- 3. All treated lumber shall bear the mark of a code recognized third party agency such as the AWPA.

#### D. PLYWOOD:

Grade: CDX or Cyme exterior Grade. Description: 5/8" thick

#### Ε. WOOD SIDING:

1. T 111 or approved equal.

#### 2.2 **MECHANICAL FASTENERS:**

#### WOOD TO STEEL: Α.

- 1. Acceptable Manufacturers:
  - Roofgrip screw with Climaseal coating; plastic disc Buildex Div. of ITW, а. Itasca, IL.
  - b. Dekfast screw with Sentri coating: plastic disc – Construction Fasteners. Inc., Wyomissing, PA.
  - Fabco Fastening Systems, West Newton, PA: Insul-Fixx screw with c. Fabcote coating; plastic plate, Plate-Fixx screw with Fabcote coat; plastic disc.
  - Kwik-Deck screw with Oxyseal coating; plastic disc Atlas Bolt & Screw d. Div., Trans Union Fastener Corp., Ashland, OH.
  - Olympic #12-11 Standard Steel Deck Screw or #14-10 Heavy Duty All e. Purpose Screw with CR-10 coating; three inch diameter plastic - Ólympic Manufacturing Group, Inc., Agawam, MA.
  - Glasfast (plastic disc) Owens-Corning Fiberglas Corp., Toledo, OH. f.

Perma Fastener screw with permaseal coating; plastic plate -International Permalite, Inc., Oak Brook, IL.

- 2. Screw Length: Sufficient to engage steel, wood deck 1 inch.

SECTION 06 10 00 - ROUGH CARPENTRY. Bid No.012022-Roof Coating Projects at Multiple School Sites

#### B. WOOD TO WOOD:

- 1. Type: Galvanized, common, annular ring nail. Length: Sufficient to penetrate underlay blocking 1-1/4 inches.
- 2. Acceptable Manufacturers:
  - a. Hillwood Manufacturing Co., Cleveland, OH.
  - b. Independent Nail, Inc., Bridgewater, MA.
  - c. W.H. Maze Co., Peru, IL.
  - d. National Nail Corp., Grand Rapids, MI.

#### C. WOOD TO MASONRY:

- 1. Acceptable Manufacturers:
  - a. Tapcon 1/4" diameter, Phillips pan head anchor Buildex Div. of ITW, Itasca, IL.
  - b. Confas Construction Fasteners, Inc., Wyomissing, PA.
  - c. Con-fixx Fabco Fastening Systems, West Newton, PA.
  - d. #14-10 Heavy Duty all Purpose Screw Olympic Manufacturing Group, Inc., Agawam, MA.
  - e. Tru-Fast fastener (stainless steel) The Tru-Fast Corp.,

Bryan, OH.

2. Length: Sufficient to provide 1-1/2 inch embedment.

#### D. WOOD TO HOLLOW MASONRY:

- 1. Acceptable Manufacturers:
  - a. Sleeve Anchor by Hilti Fastening Systems, Tulsa, OK.
  - b. Rawly Hollow Masonry Anchor by the Rawlplug Co., Inc., New Rochelle, NY.
- 2. Length: As recommended by manufacturer

#### PART 3 - EXECUTION

#### 3.1 CARPENTRY:

- A. At roof edge to receive metal fascia, around all roof top penetration perimeters, and under any flashing component that is to have a roof flange mechanically fastened to roofing substrate; mechanically attach wood blocking. Blocking thickness: Equal to common 1 x 4", 1 x 6" 2x4", 2x6", 2x8", 2x10", 2x12".
- B. Fasteners shall be installed in two rows staggered. Spacing in any one row shall not exceed 24 inches. Within eight feet of outside corners, spacing shall not exceed twelve inches in any one row.
- C. Where required, offset blocking layers twelve inches, weave corners.
- D. When preservative treated wood is cut, the cut end shall be treated in accordance with AWPA Specification M4.
- E. Lumber shall be accurately cut to the work requirements and shall be well fastened.

SECTION 06 10 00 – ROUGH CARPENTRY. Bid No.012022-Roof Coating Projects at Multiple School Sites F. Bolted fastenings shall have washers of adequate size under both heads and nuts. Nails shall be of correct size and quantity for proper fastening. Oversized nails that will result in splitting shall not be used. All fasteners shall be galvanized per ASTM A 153.

#### **END OF SECTION**

#### SECTION 07 56 40 FLUID APPLIED ROOFING RESTORATION

#### **1.GENERAL**

#### 1.1. SECTION INCLUDES

- A. Includes all labor, materials, and equipment to install an acrylic restoration coating over the properly prepared substrate.
- B. See section 011100 Summary of Work for a detailed scope of work.

#### 1.2. RELATED SECTIONS

- A. Section 01110 Summary of Work
- B. Section 06100 Rough Carpentry
- C. Section 07620 Sheet Metal Flashing and Trim

#### 1.3. REFERENCES

- A. ASTM C 920 Standard Specification for Elastomeric Joint Sealants.
- B. ASTM C 1250 Standard Test Method for Nonvolatile Content of Cold Liquid-Applied Elastomeric Waterproofing Membranes.
- C. ASTM D 1863 Standard Specification for Mineral Aggregate Used on Built-Up Roofs.
- D. ASTM D 4479 Standard Specification for Asphalt Roof Coatings Asbestos-Free.
- E. ASTM E 1980 Standard Practice for Calculating Solar Reflectance Index of Horizontal and Low-Sloped Opaque Surfaces
- F. ASTM G 21 Standard Practice for Determining Resistance of Synthetic Polymeric Materials to Fungi.
- G. SRI Solar Reflectance Index calculated according to ASTM E 1980.
- H. South Coast AQMD Standards.
- I. SMACNA Architectural Sheet Metal Manual.
- J. ANSI/SPRI ES-1 Testing and Certification Listing of Shop Fabricated Edge Metal
- K. National Roofing Contractors Association (NRCA) Roofing and Waterproofing Manual.

#### 1.4. SYSTEM DESCRIPTION

- A. Mineral Surface Roof Restoration: Renovation work includes:
  - 1. Surface preparation: Pressure wash the existing surface remove dirt, and debris.
  - 2. Fascia/Gravel Stop Edges: Cut back edges, prime, three course with mastic & mesh, install white roofing granules into fresh mastic.
  - 3. Parapets and Vertical Surfaces: Repair as needed, prime, three course with mastic & mesh all laps, corners & transitions. Install white roofing granules into fresh mastic.
  - 4. Metal Flashings: Repair/Replace metal flashings, pitch pockets, etc.
  - 5. Roof Repairs: Repair blisters, stressed or cracked membrane. Cut back, patch with

- primer/mastic/membrane.
- 6. Primer: Prime entire roof surface.
- 7. Coating: Install white acrylic coating over the entire roof surface.

#### 1.5. SUBMITTALS

- A. Submit under provisions of Section 013000.
- B. Product Data: Manufacturer's data sheets on each product to be used, including:
  - 1. Preparation instructions and recommendations.
  - 2. Storage and handling requirements and recommendations.
  - 3. Installation methods.
- C. Shop Drawings: Submit shop drawings including installation details of roofing, flashing, fastening, insulation and vapor barrier, including notation of roof slopes and fastening patterns of insulation and base modified bitumen membrane, prior to job start.
- D. LEED Submittals: Provide documentation of how the requirements of Credit will be met:
  - List of proposed materials with recycled content. Indicate post-consumer recycled content and pre-consumer recycled content for each product having recycled content.
     Product data and partification percentages by weight of post.
  - 2. Product data and certification letter indicating percentages by weight of postconsumer and pre-consumer recycled content for products having recycled content.
  - Product reflectivity and emissivity criteria to qualify for one point under the LEED credit category, Credit 7.2, Landscape & Exterior Design to Reduce Heat Island -Roof.
- E. Verification Samples: For each product specified, two samples, minimum size 6 inches (150 mm) square, representing actual product, and color.
- F. Manufacturer's Certificates: Certify products meet or exceed specified requirements.
- G. Provide written certification from the roofing system manufacturer certifying the applicator is currently authorized to install the specified roof system and ability to provide the specified warranty.
- H. Sample Warranty: Provide an unexecuted copy of the warranty specified for this project clearly stating the terms required of the owner, contractor, and manufacturer.
- I. Closeout Submittals: Provide manufacturer's maintenance instructions that include recommendations for periodic inspection and maintenance of all completed roofing work. Provide product warranty executed by the manufacturer. Assist Owner in preparation and submittal of roof installation acceptance certification as may be necessary in connection with fire and extended coverage insurance on roofing and associated work.

#### 1.6. QUALITY ASSURANCE

- A. Perform Work in accordance with NRCA Roofing and Waterproofing Manual.
- B. Manufacturer Qualifications: Manufacturer: Company specializing in manufacturing products specified in this section with documented ISO 9001 certification and minimum twelve years and experience.
- C. Installer Qualifications: Company specializing in performing Work of this section with minimum five years documented experience and a certified Pre-Approved Garland Contractor.
- D. Installer's Field Supervision: Maintain a full-time Supervisor/Foreman on job site during all phases of roofing work while roofing work is in progress.
- E. Product Certification: Provide manufacturer's certification that materials are manufactured in

the United States and conform to requirements specified herein, are chemically and physically compatible with each other, and are suitable for inclusion within the total roof system specified herein.

F. Source Limitations: Obtain all components of roof system from a single manufacturer. Secondary products that are required shall be recommended and approved in writing by the roofing system Manufacturer. Upon request of the Architect or Owner, submit Manufacturer's written approval of secondary components in list form, signed by an authorized agent of the Manufacturer.

#### 1.7. PRE-INSTALLATION CONFERENCE

- A. Convene a pre-roofing conference approximately two weeks before scheduled commencement of roofing system installation and associated work.
- B. Require attendance of installers of deck or substrate construction to receive roofing, installers of rooftop units and other work in and around roofing which must precede or follow roofing work including mechanical work, Architect, Owner, roofing system manufacturer's representative.
- C. Objectives include:
  - 1. Review foreseeable methods and procedures related to roofing work, including set up and mobilization areas for stored material and work area.
  - 2. Tour representative areas of roofing substrates, inspect and discuss condition of substrate, roof drains, curbs, penetrations and other preparatory work.
  - 3. Review structural loading limitations of deck and inspect deck for loss of flatness and for required attachment.
  - 4. Review roofing system requirements, Drawings, Specifications and other Contract Documents.
  - 5. Review and finalize schedule related to roofing work and verify availability of materials, installer's personnel, equipment and facilities needed to make progress and avoid delays.
  - 6. Review required inspection, testing, certifying procedures.
  - 7. Review weather and forecasted weather conditions and procedures for coping with unfavorable conditions, including possibility of temporary roofing.
  - 8. Record conference including decisions and agreements reached. Furnish a copy of records to each party attending.

#### 1.8. DELIVERY, STORAGE, AND HANDLING

- A. Deliver and store products in manufacturer's unopened packaging with labels intact until ready for installation.
- B. Store all roofing materials in a dry place, on pallets or raised platforms, out of direct exposure to the elements until time of application. Store materials at least 4 inches above ground level and covered with "breathable" tarpaulins.
- C. Stored in accordance with the instructions of the manufacturer prior to their application or installation. Store roll goods on end on a clean flat surface. No wet or damaged materials will be used in the application.
- D. Store at room temperature wherever possible, until immediately prior to installing the roll. During winter, store materials in a heated location with a 50 degree F (10 degree C) minimum temperature, removed only as needed for immediate use. Keep materials away from open flame or welding sparks.
- E. Avoid stockpiling of materials on roofs without first obtaining acceptance from the Architect/ Engineer.
- F. Adhesive storage shall be between the range of above 50 degree F (10 degree C) and

below 80 degree F (27 degree C). Area of storage shall be constructed for flammable storage.

#### 1.9. PROJECT CONDITIONS

- A. Maintain environmental conditions (temperature, humidity, and ventilation) within limits recommended by manufacturer for optimum results. Do not install products under environmental conditions outside manufacturer's absolute limits.
- B. Weather Condition Limitations: Do not apply roofing system during inclement weather or when a 40 percent chance of precipitation or greater is expected.
- C. Proceed with roofing work only when existing and forecasted weather conditions will permit unit of work to be installed in accordance with manufacturer's recommendations and warranty requirements.
- D. Do not expose materials vulnerable to water or sun damage in quantities greater than can be weatherproofed during same day.
- E. When applying materials with spray equipment, take precautions to prevent over spray and/ or solvents from damaging or defacing surrounding walls, building surfaces, vehicles or other property. Care should be taken to do the following:
  - 1. Close air intakes into the building.
  - 2. Have a dry chemical fire extinguisher available at the jobsite.
  - 3. Post and enforce "No Smoking" signs.
- F. Avoid inhaling spray mist; take precautions to ensure adequate ventilation.
- G. Protect completed roof sections from foot traffic for a period of at least 48 hours at 75 degrees F (24 degrees C) and 50 percent relative humidity or until fully cured.
- H. Take precautions to ensure that materials do not freeze.
- I. Minimum temperature for application is 40 degrees F (4 degrees C) and rising for solvent based materials and 50 degrees F (10 degrees C) and rising for water based.

#### 1.10. WARRANTY

- A. Upon completion of the work, provide the Manufacturer's Warranty.
  - 1. Warranty Period:
    - a. 5 years from date of acceptance.
- B. Installer is to guarantee all work against defects in materials and workmanship for a period indicated following final acceptance of the Work.
  - 1. Warranty Period:
    - a. 3 years from date of acceptance.

#### 2.PRODUCTS

#### 2.1. MANUFACTURERS

- A. Acceptable Manufacturer: Garland Company, Inc. (The), which is located at: 3800 E. 91st St.; Cleveland, OH 44105; Local Representative: Richard Jones: (559) 647-1196 rjones@garlandind.com Web Site:www.garlandco.com
- B. Requests for substitutions will not be considered for this project.

#### 2.2. ROOF RESTORATION SYSTEM MINERAL SURFACE ROOFS

- A. Asphalt Primer: Install primer at a rate of ½ gallon per 100 square feet at all areas to be three coursed.
  1. Garla Prime VOC
- B. Acrylic Primer: Install at a rate of 1/2 gallon per 100 square feet to all roof areas.
- C. Coating Base Coat: Install at a rate of 1.5 gallons per 100 square feet. 1. Coating: Pyramic Plus Lo
- D. Coating Top Coat. Install at a rate of 1.5 gallons per 100 square feet. 1. Coating: Pyramic Plus Lo
- E. Mastic: Install three course treatment at all penetrations and wall flashing laps.
   1. Flashing Bond Mastic
- F. Mesh: Install three course treatment at all penetrations and wall flashing laps. 1. Garmesh 6"

#### 2.3. ACCESSORIES:

- A. Nails and Fasteners: Non-ferrous metal or galvanized steel, except that hard copper nails shall be used with copper; aluminum or stainless steel nails shall be used with aluminum; and stainless steel nails shall be used with stainless steel, Fasteners shall be self-clinching type of penetrating type as recommended by the deck manufacturer. Fasten nails and fasteners flush-driven through flat metal discs not less than 1 inch (25 mm) diameter. Omit metal discs when one-piece composite nails or fasteners with heads not less than 1 inch (25 mm) diameter are used.
- B. Urethane Sealant Tuff-Stuff: One part, non-sag sealant as approved and furnished by the membrane manufacturer for moving joints.
  - 1. Tensile Strength, ASTM D 412: 250 psi
  - 2. Elongation, ASTM D 412: 950%
  - 3. Hardness, Shore A ASTM C 920: 35
  - 4. Adhesion-in-Peel, ASTM C 92: 30 pli
- C. Pitch Pocket Sealer Seal-Tite: Two part, 100% solids, self-leveling, polyurethane sealant for filling pitch pans as recommended and furnished by the membrane manufacturer.
  - 1. Durometer, ASTM D 2240: 40-50 Shore
  - 2. Elongation, ASTM D 412: 250%
  - 3. Tensile Strength, ASTM D 412: 200 @ 100 mil

#### 2.4. EDGE TREATMENT AND ROOF PENETRATION FLASHINGS

- A. Flashing Boot Rubbertite Flashing Boot: Neoprene pipe boot for sealing single or multiple pipe penetrations adhered in approved adhesives as recommended and furnished by the membrane manufacturer.
- B. Vents and Breathers: Heavy gauge aluminum and fully insulated vent that allows moisture and air to escape but not enter the roof system as recommended and furnished by the membrane manufacturer.
- C. Pitch pans, Rain Collar 24 gauge stainless or 20oz (567gram) copper. All joints should be welded/soldered watertight. See details for design.
- D. Drain Flashings should be 4lb (1.8kg) sheet lead formed and rolled.
- E. Plumbing stacks should be 4lb (1.8kg) sheet lead formed and rolled.

- F. Liquid Flashing Tuff-Flash: An asphaltic-polyurethane, low odor, liquid flashing material designed for specialized details unable to be waterproofed with typical modified membrane flashings.
  - 1. Tensile Strength, ASTM D 412: 400 psi
  - 2. Elongation, ASTM D 412: 300%
  - 3. Density @77 degrees F 8.5 lb/gal typical
- G. Fabricated Flashings: Fabricated flashings and trim are specified in Section 07620.
  - Fabricated flashings and trim shall conform to the detail requirements of SMACNA "Architectural Sheet Metal Manual" and/or the CDA Copper Development Association "Copper in Architecture - Handbook" as applicable.
- H. Manufactured Roof Specialties: Manufactured copings, fascia, gravel stops, control joints, expansion joints, joint covers and related flashings and trim are specified in Section 07710.
  - 1. Manufactured roof specialties shall conform to the detail requirements of SMACNA "Architectural Sheet Metal Manual" and/or the NRCA "Roofing and Waterproofing Manual" as applicable.

#### **3.EXECUTION**

#### 3.1. EXAMINATION

- A. Do not begin installation until substrates have been properly prepared.
- B. Verify that work penetrating the roof deck, or which may otherwise affect the roofing, has been properly completed.
- C. If substrate preparation is the responsibility of another installer, notify Architect of unsatisfactory preparation before proceeding.

#### 3.2. ROOF PREPARATION AND REPAIR

- A. General:
  - 1. Repair existing roof flashings at curbs and parapet walls
  - 2. Remove all wet, deteriorated, blistered or delaminated roofing membrane or insulation and fill in any low spots occurring as a result of removal work to create a smooth, even surface for application of new roof membranes.
  - 3. Install new wood nailers as necessary to accommodate insulation/recovery board or new nailing patterns.
  - 4. Existing roof surfaces shall be primed as necessary and allowed to dry prior to installing the roofing system.
- B. Prepare surfaces using the methods recommended by the manufacturer for achieving the best result for the substrate under the project conditions.
- C. Repair all defects such as deteriorated roof decks; replace saturated insulation board, replace loose or brittle membrane or membrane flashings. Verify that exiting conditions meet the following requirements:
  - 1. Existing membrane is either fully adhered or that the membranes mechanical fasteners are secured and functional.
  - 2. Application of roofing materials over a brittle roof membrane is not recommended.
- D. Remove all loose dirt and foreign debris from the roof surface. Do not damage roof membrane in cleaning process.
- E. Clean and seal all parapet walls, gutters and coping caps, and repair any damaged metal where necessary. Seal watertight all fasteners, pipes, drains, vents, joints and penetrations where water could enter the building envelope.
- F. Clean the entire roof surface by removing all dirt, algae, paint, oil, talc, rust or foreign

substance. Use a 10 percent solution of TSP (tri-sodium phosphate), Simple Green and warm water. Scrub heavily soiled areas with a brush. Rinse with fresh water to remove all TSP solution. Allow roof to dry thoroughly before continuing.

G. Repair existing roof membrane as necessary to provide a sound substrate for the liquid membrane. All surface defects (cracks, blisters, tears) must be repaired with similar materials.

#### 3.3. INSTALLATION

- A. General Installation Requirements:
  - 1. Install in accordance with manufacturer's instructions. Apply to minimum coating thickness required by the manufacturer.
  - 2. Cooperate with manufacturer, inspection and test agencies engaged or required to perform services in connection with installing the roof system.
  - 3. Insurance/Code Compliance: Where required by code, install and test the roofing system to comply with governing regulation and specified insurance requirements.
  - Protect work from spillage of roofing materials and prevent materials from entering or clogging drains and conductors. Replace or restore work damaged by installation of the roofing system.
  - 5. All primers must be top coated within 24 hours of application. Re-prime If more time passes after priming.
  - 6. Keep roofing materials dry during application. Phased construction can be allowed as long as no, more than 7 days pass between coats excluding primers.
  - 7. Coordinate counter flashing, cap flashings, expansion joints and similar work with work specified in other Sections under Related Work.
  - 8. Coordinate roof accessories and miscellaneous sheet metal accessory items, including piping vents and other devices with work specified in other Sections under Related Work.
- B. Mineral Surface Roof Restoration: Renovation work includes:
  - 1. Surface preparation: Pressure wash the existing surface remove dirt, and debris.
  - 2. Fascia/Gravel Stop Edges: Cut back edges 2", prime with Garla-Prime VOC allow to dry, three course with Flashing Bond mastic & Garmesh, install white roofing granules into fresh mastic.
  - 3. Parapets and Vertical Surfaces: Repair as needed, prime with Garla Prime VOC, three course with Flashing Bond mastic & Garmesh all laps, corners & transitions. Install white roofing granules into fresh mastic.
  - 4. Metal Flashings: Repair/Replace metal flashings, pitch pockets, etc.
  - 5. Roof Repairs: Repair blisters, stressed or cracked membrane. Cut back, patch with Garla Prime VOC primer/ Flashing Bond mastic/Stressply membrane.
  - 6. Primer: Prime entire roof surface with Garla-Block primer.
  - 7. Coating: Install Pyramic white acrylic coating over the entire roof surface at a rate of 1.5 gallons per 100 sq ft base coat and 1.5 gallons per 100 sq ft top coat.
    - a. Apply Pyramic Acrylic Coating in a uniform manner.
    - b. Use special attention to coating flashings and other critical areas to build adequate membrane thickness.
    - c. Use multiple coats on verticals to prevent sagging.
    - d. Apply at 3.0 gallons per 100 sq ft. over the entire roof surface in two coats.

#### 3.4. INSTALLATION EDGE TREATMENT AND ROOF PENETRATION FLASHING

- A. Fabricated Flashings: Fabricated flashings and trim are provided as specified in Section 07620.
  - 1. Fabricated flashings and trim shall conform to the detail requirements of SMACNA "Architectural Sheet Metal Manual" and/or the Copper Development Association "Copper in Architecture - Handbook" as applicable.

075640-7

- B. Manufactured Roof Specialties: Manufactured copings, fascia, gravel stops, control joints, expansion joints, joint covers and related flashings and trim are provided as specified in Section 07710.
  - 1. Manufactured roof specialties shall conform to the detail requirements of SMACNA "Architectural Sheet Metal Manual" and/or the National Roofing Contractor's Association "Roofing and Waterproofing Manual" as applicable.
- C. Metal Edge:
  - 1. Inspect the nailers to assure proper attachment and configuration.
  - 2. Run one ply over the edge. Assure coverage of all wood nailers. Fasten plies with ring shank nails at 8 inches (203 mm) o.c.
  - 3. Install continuous cleat and fasten at 6 inches (152 mm) o.c.
  - 4. Install new metal edge hooked to continuous cleat and set in bed of roof cement. Fasten flange to wood nailers every 3 inches (76 mm) o.c. staggered.
  - 5. Prime metal edge at a rate of 100 square feet per gallon and allow to dry.
  - 6. Strip in flange with base flashing ply covering entire flange in bitumen with 6 inches (152 mm) on to the field of roof. Assure ply laps do not coincide with metal laps.
  - Install a second ply of modified flashing ply in bitumen over the base flashing ply, 9 inches (228 mm) on to the field of the roof. Seal outside edge with rubberized cement.
- D. Coping Cap:
  - 1. Minimum flashing height is 8 inches (203 mm) above finished roof height. Maximum flashing height is 24 inches (609 mm). Prime vertical wall at a rate of 100 square feet per gallon and allow to dry.
  - 2. Set cant in bitumen. Run all field plies over cant a minimum of 2 inches (50 mm).
  - Install base flashing ply covering entire wall and wrapped over top of wall and down face with 6 inches (152 mm) on to field of the roof and set in cold asphalt. Nail membrane at 8 inches (203 mm) o.c.
  - 4. Install a second ply of modified flashing ply in bitumen over the base flashing ply, 9 inches (228 mm) on to the field of the roof. Apply a three-course application of mastic and mesh at all seams and allow to cure and install white roofing granules into the fresh mastic.
  - 5. Install coping cap per manufacturer's recommendations.
- E. Surface Mounted Counterflashing:
  - Minimum flashing height is 8 inches (203 mm) above finished roof height. Maximum flashing height is 24 inches (609 mm). Prime vertical wall at a rate of 100 square feet per gallon and allow to dry.
  - 2. Set cant in bitumen. Run all field plies over cant a minimum of 2 inches (50 mm).
  - 3. Install base flashing ply covering wall set in bitumen with 6 inches (152 mm) on to field of the roof.
  - 4. Install a second ply of modified flashing ply in bitumen over the base flashing ply, 9 inches (228 mm) on to the field of the roof. Apply a three-course application of mastic and mesh at all vertical seams and allow to cure and install white roofing granules into the fresh mastic.
  - 5. Apply butyl tape to wall behind flashing. Secure termination bar through flashing, butyl tape and into wall. Alternatively use caulk to replace the butyl tape.
  - 6. Secure counterflashing set on butyl tape above flashing at 8 inches (203 mm) o.c. and caulk top of counterflashing.
- F. Curb Detail/Air Handling Station:
  - 1. Minimum curb height is 8 inches (203 mm) above finished roof height. Prime vertical at a rate of 100 square feet per gallon and allow to dry.
  - 2. Set cant in bitumen. Run all field plies over cant a minimum of 2 inches (50 mm).
  - 3. Install base flashing ply covering curb set in bitumen with 6 inches (152 mm) on to field of the roof.
  - 4. Install a second ply of modified flashing ply in bitumen over the base flashing ply, 9 inches (228 mm) on to the field of the roof. Apply a three-course application of mastic and mesh at all vertical seams and allow to cure and install white roofing granules into

#### 075640-8

the fresh mastic.

- 5. Install pre-manufactured counterflashing with fasteners and neoprene washers or per manufacturer's recommendations.
- 6. Set equipment on neoprene pad and fasten as required by equipment manufacturer.
- G. Roof Drain Alternate:
  - 1. Plug drain to prevent debris from entering plumbing.
  - 2. Taper insulation to drain minimum of 24 inches (609 mm) from center of drain.
  - 3. Install two base flashing plies (40 inch square minimum) in bitumen.
  - 4. Set lead/copper flashing (30 inch square minimum) in 1/4 inch (6 mm) bed of mastic. Run lead/copper into drain a minimum of 2 inches (50 mm). Prime lead/copper at a rate of 100 square feet per gallon and allow to dry.
  - 5. Run roof system plies over drain. Cut out plies inside drain bowl.
  - 6. Install modified membrane (48 inch square minimum) in bitumen.
  - 7. Install clamping ring and assure that all plies are under the clamping ring.
  - 8. Remove drain plug and install strainer.
- H. Plumbing Stack:
  - 1. Minimum stack height is 12 inches (609 mm).
  - 2. Run roof system over the entire surface of the roof. Seal the base of the stack with elastomeric sealant.
  - 3. Prime flange of new sleeve. Install properly sized sleeves set in 1/4 inch (6 mm) bed of roof cement.
  - 4. Install base flashing ply in bitumen.
  - 5. Install membrane in bitumen.
  - 6. Caulk the intersection of the membrane with elastomeric sealant.
  - 7. Turn sleeve a minimum of 1 inch (25 mm) down inside of stack.

#### 3.5. CLEANING

- A. Clean-up and remove daily from the site all wrappings, empty containers, paper, loose particles and other debris resulting from these operations.
- B. Remove asphalt markings from finished surfaces.
- C. Repair or replace defaced or disfigured finishes caused by Work of this section.

#### 3.6. PROTECTION

- A. Provide traffic ways, erect barriers, fences, guards, rails, enclosures, chutes and the like to protect personnel, roofs and structures, vehicles and utilities.
- B. Protect exposed surfaces of finished walls with tarps to prevent damage.
- C. Plywood for traffic ways required for material movement over existing roofs shall be not less than 5/8 inch (16 mm) thick.
- D. In addition to the plywood listed above, an underlayment of minimum 1/2 inch (13 mm) recover board is required on new roofing.
- E. Special permission shall be obtained from the Manufacturer before any traffic shall be permitted over new roofing.

#### 3.7. FIELD QUALITY CONTROL

- A. Require attendance of roofing materials manufacturers' representatives at site during installation of the roofing system a minimum of two (2) days per week.
- B. Perform field inspection as required under provisions of manufacturers requirements.

C. Correct defects or irregularities discovered during field inspection.

#### 3.8. FINAL INSPECTION

- A. At completion of roofing installation and associated work, meet with Contractor, Architect, installer, installer of associated work, roofing system manufacturer's representative and others directly concerned with performance of roofing system.
- B. Walk roof surface areas, inspect perimeter building edges as well as flashing of roof penetrations, walls, curbs and other equipment. Identify all items requiring correction or completion and furnish copy of list to each party in attendance.
- C. If core cuts verify the presence of damp or wet materials, the installer shall be required to replace the damaged areas at his own expense.
- D. Repair or replace deteriorated or defective work found at time above inspection as required to a produce an installation that is free of damage and deterioration at time of Substantial Completion and according to warranty requirements.
- E. Architect upon completion of corrections.
- F. Following the final inspection, provide written notice of acceptance of the installation from the roofing system manufacturer.

#### 3.9. PROTECTION

- A. Protect installed products until completion of project.
- B. Touch-up, repair or replace damaged products before Substantial Completion.

#### 3.10. SCHEDULES

- A. Coating:
  - 1. Pyramic: White Elastomeric Roof Coating
    - a. Pyramic Plus Lo Acrylic Roof Coating: White, Non Toxic, Fire Retardant Roof Coating.
      - 1. Non Volatile 63%
      - 2. Density 11.7lb. / gal
      - 3. VOC <50 gal./l
      - 4. Reflectance 0.83
      - 5. Emittance 0.90
      - 6. SRI 104

#### 3.11. OWNER SUPPLIED MATERIALS

- A. The district will only supply the quantity listed in the owner supplied materials section 016400. All additional materials and accessories will be the full responsibility of the contractor to provide and install per the specification and project requirements.
- B. Any material or accessories required for the installation of the roof system in excess of the district provided material must be supplied by the Contractor and added into the bid cost proposal. It is up to the Contractor to determine the precise amount of material required for the completion of this project; and to provide excess material, as required. The cost to handle and break flashing metal from the District provided flat stock is contractor's responsibility and to be added into the bid cost proposal.
- C. All required flashings as required per each specification section for plumbing, electrical, gas, etc. will be the Contractors responsibility to provide and install as well as to be included in

the bid cost.

- D. All materials not specifically included in the owner supplied materials section will be the responsibility of the contractor to provide and install in compliance with section 075640.
- E. Freight charges of owner supplied materials will be the responsibility of the owner. Contractor must unload delivery of materials, properly protect, cover and store at job site.
- F. Contractor must be able to provide certification in writing from roof system manufacturer that the contractor is approved to install the specified roof system and provide all warranty requirements of section 075640.
- B. Materials specifically provided by the Owner;
  - 1. See specification section 01 64 00 Owners Supplied Materials

END OF SECTION

#### SECTION 07 62 00

#### SHEET METAL FLASHING AND TRIM

#### 1.GENERAL

#### 1. RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 2. SUMMARY

- A. Section Includes:
  - 1. Manufactured through-wall flashing with counter flashing.
  - 2. Formed low-slope roof sheet metal fabrications.
  - 3. Formed wall, coping, and soffit sheet metal fabrications.
  - 4. Formed equipment support flashing
  - 5. Surface mounted counter flashing
  - 6. Manufactured reglets and counter flashing
  - 7. Formed gutter and downspouts
- B. Related Requirements:
  - 1. Division 06 "Rough Carpentry" for wood nailers, curbs, and blocking.
  - Division 07 "Membrane Roofing" for materials and installation of sheet metal flashing and trim integral with roofing.
  - 3. Division 07 "Metal Roofing" for materials and installation of sheet metal flashing and trim integral with roofing.
  - 4. Division 07 "Roof Accessories" for set-on-type curbs, equipment supports, roof hatches, vents, and other manufactured roof accessory units.

#### 3. COORDINATION

- A. Coordinate sheet metal flashing and trim layout and seams with sizes and locations of penetrations to be flashed, and joints and seams in adjacent materials.
- B. Coordinate sheet metal flashing and trim installation with adjoining roofing and wall materials, joints, and seams to provide leak proof, secure, and noncorrosive installation.

#### 4. PREINSTALLATION MEETINGS

- A. Pre Installation Conference: Conduct conference at Project site.
  - 1. Review construction schedule. Verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
  - 2. Review special roof details, roof drainage, roof-penetration flashing, equipment curbs, and condition of other construction that affect sheet metal flashing and trim.

- 3. Review requirements for insurance and certificates if applicable.
- 4. Review sheet metal flashing observation and repair procedures after flashing installation.

#### 5. SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each manufactured product and accessory.
- B. Shop Drawings: For sheet metal flashing and trim.
  - 1. Include plans, elevations, sections, and attachment details.
  - 2. Detail fabrication and installation layouts, expansion-joint locations, and keyed details. Distinguish between shop- and field-assembled work.
  - 3. Include identification of material, thickness, weight, and finish for each item and location in Project.
  - 4. Include details for forming, including profiles, shapes, seams, and dimensions.
  - 5. Include details for joining, supporting, and securing, including layout and spacing of fasteners, cleats, clips, and other attachments. Include pattern of seams.
  - 6. Include details of termination points and assemblies.
  - 7. Include details of expansion joints and expansion-joint covers, including showing direction of expansion and contraction from fixed points.
  - 8. Include details of roof-penetration flashing.
  - 9. Include details of edge conditions, including eaves, ridges, valleys, rakes, crickets, and counter flashings as applicable.
  - 10. Include details of special conditions.
  - 11. Include details of connections to adjoining work.
  - 12. Detail formed flashing and trim at scale of not less than 3 inches per 12 inches
- C. Samples for Initial Selection: For each type of sheet metal and accessory indicated with factory-applied finishes.
- D. Samples for Verification: For each type of exposed finish.
  - 1. Sheet Metal Flashing: 12 inches (300 mm) long by actual width of unit, including finished seam and in required profile. Include fasteners, cleats, clips, closures, and other attachments.
  - 2. Trim, Metal Closures, Expansion Joints, Joint Intersections, and Miscellaneous Fabrications: 12 inches (300 mm) long and in required profile. Include fasteners and other exposed accessories.

#### 6. INFORMATIONAL SUBMITTALS

- A. Qualification Data: For fabricator.
- B. Product Certificates: For each type of coping and roof edge flashing that is SPRI ES-1 tested.
- C. Product Test Reports: For each product, for tests performed by a qualified testing agency.

D. Sample Warranty: For special warranty.

#### 7. CLOSEOUT SUBMITTALS

A. Maintenance Data: For sheet metal flashing and trim, and its accessories, to include in maintenance manuals.

#### 8. QUALITY ASSURANCE

- A. Fabricator Qualifications: Employs skilled workers who custom fabricate sheet metal flashing and trim similar to that required for this Project and whose products have a record of successful in-service performance.
  - 1. For copings and roof edge flashings that are SPRI ES-1 tested, shop shall be listed as able to fabricate required details as tested and approved.

#### 9. DELIVERY, STORAGE, AND HANDLING

- A. Do not store sheet metal flashing and trim materials in contact with other materials that might cause staining, denting, or other surface damage. Store sheet metal flashing and trim materials away from uncured concrete and masonry.
- B. Protect strippable protective covering on sheet metal flashing and trim from exposure to sunlight and high humidity, except to extent necessary for period of sheet metal flashing and trim installation.

#### 10. WARRANTY

- A. Special Warranty on Finishes: Manufacturer agrees to repair finish or replace sheet metal flashing and trim that shows evidence of deterioration of factory-applied finishes within specified warranty period.
  - 1. Exposed Panel Finish: Deterioration includes, but is not limited to, the following:
    - a. Color fading more than 5 Hunter units when tested according to ASTM D 2244.
    - b. Chalking in excess of a No. 8 rating when tested according to ASTM D 4214.
    - c. Cracking, checking, peeling, or failure of paint to adhere to bare metal.
  - 2. Finish Warranty Period: **20** years from date of Substantial Completion.

#### 2.PRODUCTS

#### 1. **PERFORMANCE REQUIREMENTS**

A. General: Sheet metal flashing and trim assemblies shall withstand wind loads, structural movement, thermally induced movement, and exposure to weather without failure due to defective manufacture, fabrication, installation, or other defects in construction.

Completed sheet metal flashing and trim shall not rattle, leak, or loosen, and shall remain watertight.

- B. Sheet Metal Standard for Flashing and Trim: Comply with NRCA's "The NRCA Roofing Manual" and SMACNA's "Architectural Sheet Metal Manual" requirements for dimensions and profiles shown unless more stringent requirements are indicated.
- C. Sheet Metal Standard for Copper: Comply with CDA's "Copper in Architecture Handbook." Conform to dimensions and profiles shown unless more stringent requirements are indicated.
- D. SPRI Wind Design Standard: Manufacture and install roof edge flashings tested according to SPRI ES-1 and capable of resisting the following design pressure:
  - 1. Design Pressure: As indicated on Drawings.
- E. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes to prevent buckling, opening of joints, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.
  - 1. Temperature Change: 120 deg F (67 deg C), ambient; 180 deg F (100 deg C), material surfaces.

#### 2. SHEET METALS

- A. General: Protect mechanical and other finishes on exposed surfaces from damage by applying strippable, temporary protective film before shipping.
- B. Metallic-Coated Steel Sheet: Provide zinc-coated (galvanized) steel sheet according to ASTM A 653/A 653M, G90 (Z275) coating designation; prepainted by coil-coating process to comply with ASTM A 755/A 755M.
  - 1. Surface: Smooth, flat and with manufacturer's standard clear acrylic coating on both sides.
  - 2. Exposed Coil-Coated Finish:
    - a. Two-Coat Fluoropolymer: AAMA 621. Fluoropolymer finish containing not less than 70 percent PVDF resin by weight in both color coat and clear topcoat. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.
  - 3. Color: Match Architect's sample
  - 4. Concealed Finish: Pretreat with manufacturer's standard white or light-colored acrylic or polyester backer finish, consisting of prime coat and wash coat with minimum total dry film thickness of 0.5 mil (0.013 mm).

#### 3. UNDERLAYMENT MATERIALS

A. Self-Adhering, High-Temperature Sheet: Minimum 45 mils thick, consisting of a slip-resistant polyethylene- or polypropylene-film top surface laminated to a layer of butyl- or SBS-modified asphalt adhesive, with release-paper backing; specifically designed to withstand high metal temperatures beneath metal roofing. Provide primer according to written recommendations of underlayment manufacturer.

- 1. The Garland Company Inc., 3800 E. 91<sup>st</sup> Street Cleveland OH 44105; R-Mer Seal self-adhering underlayment.
- 2. Thermal Stability: ASTM D 1970; stable after testing at 240 deg F or higher.
- 3. Low-Temperature Flexibility: ASTM D 1970; passes after testing at minus 20 deg F or lower.
- B. Slip Sheet: Rosin-sized building paper, 3 lb/100 sq. ft. minimum.

#### 4. MISCELLANEOUS MATERIALS

- A. General: Provide materials and types of fasteners, solder, protective coatings, sealants, and other miscellaneous items as required for complete sheet metal flashing and trim installation and as recommended by manufacturer of primary sheet metal unless otherwise indicated.
- B. Fasteners: Wood screws, annular threaded nails, self-tapping screws, self-locking rivets and bolts, and other suitable fasteners designed to withstand design loads and recommended by manufacturer of primary sheet metal or manufactured item.
  - 1. General: Blind fasteners or self-drilling screws, gasketed, with hex-washer head.
    - a. Exposed Fasteners: Heads matching color of sheet metal using plastic caps or factory-applied coating. Provide metal-backed EPDM or PVC sealing washers under heads of exposed fasteners bearing on weather side of metal.
    - b. Blind Fasteners: High-strength aluminum or stainless-steel rivets suitable for metal being fastened.
    - c. Spikes and Ferrules: Same material as gutter; with spike with ferrule matching internal gutter width.
  - 2. Fasteners for Zinc-Tin Alloy-Coated Stainless-Steel Sheet: Series 300 stainless steel.
- C. Solder:
  - 1. For Zinc-Coated (Galvanized) Steel: ASTM B 32, Grade Sn50, 50 percent tin and 50 percent lead or Grade Sn60, 60 percent tin and 40 percent lead with maximum lead content of 0.2 percent.
- D. Sealant Tape: Pressure-sensitive, 100 percent solids, polyisobutylene compound sealant tape with release-paper backing. Provide permanently elastic, nonsag, nontoxic, nonstaining tape 1/2 inch wide and 1/8 inch thick.
- E. Elastomeric Sealant: ASTM C 920, elastomeric polyurethane polymer sealant; of type, grade, class, and use classifications required to seal joints in sheet metal flashing and trim and remain watertight.
- F. Butyl Sealant: ASTM C 1311, single-component, solvent-release butyl rubber sealant; polyisobutylene plasticized; heavy bodied for hooked-type expansion joints with limited movement.
- G. Bituminous Coating: Cold-applied asphalt emulsion according to ASTM D 1187.
- H. Asphalt Roofing Cement: ASTM D 4586, asbestos free, of consistency required for application.

#### 5. FABRICATION, GENERAL

- A. General: Custom fabricate sheet metal flashing and trim to comply with details shown and recommendations in cited sheet metal standard that apply to design, dimensions, geometry, metal thickness, and other characteristics of item required. Fabricate sheet metal flashing and trim in shop to greatest extent possible.
  - 1. Fabricate sheet metal flashing and trim in thickness or weight needed to comply with performance requirements, but not less than that specified for each application and metal.
  - 2. Obtain field measurements for accurate fit before shop fabrication.
  - 3. Form sheet metal flashing and trim to fit substrates without excessive oil canning, buckling, and tool marks; true to line, levels, and slopes; and with exposed edges folded back to form hems.
  - 4. Conceal fasteners and expansion provisions where possible. Do not use exposed fasteners on faces exposed to view.
- B. Fabrication Tolerances: Fabricate sheet metal flashing and trim that is capable of installation to a tolerance of 1/4 inch in 20 feet on slope and location lines indicated on Drawings and within 1/8-inch offset of adjoining faces and of alignment of matching profiles.
- C. Expansion Provisions: Form metal for thermal expansion of exposed flashing and trim.
  - 1. Form expansion joints of intermeshing hooked flanges, not less than 1 inch deep, filled with butyl sealant concealed within joints.
  - 2. Use lapped expansion joints only where indicated on Drawings.
- D. Sealant Joints: Where movable, nonexpansion-type joints are required, form metal to provide for proper installation of elastomeric sealant according to cited sheet metal standard.
- E. Fabricate cleats and attachment devices from same material as accessory being anchored or from compatible, noncorrosive metal.
- F. Seams: Fabricate nonmoving seams with flat-lock seams. Form seams and seal with elastomeric sealant unless otherwise recommended by sealant manufacturer for intended use.
- G. Do not use graphite pencils to mark metal surfaces.

#### 6. ROOF-DRAINAGE SHEET METAL FABRICATIONS

- A. Hanging Gutters: Fabricate to cross section required, complete with end pieces, outlet tubes, and other accessories as required. Fabricate in minimum 96-inch- long sections. Furnish flat-stock gutter brackets and flat-stock gutter spacers and straps fabricated from same metal as gutters, of size recommended by cited sheet metal standard but with thickness not less than dimension indicated on Drawings. Fabricate expansion joints, expansion-joint covers, gutter bead reinforcing bars, and gutter accessories from same metal as gutters. Shop fabricate interior and exterior corners.
  - 1. Gutter Profile: Style B according to cited sheet metal standard.
  - 2. Expansion Joints: Butt type with cover plate.
  - **3.** Accessories: Continuous, removable leaf screen with sheet metal frame and hardware cloth screen at each downspout location.
  - 4. Gutters with Girth up to 15 Inches: Fabricate from the following materials:

SECTION 07 62 00 - SHEET METAL FLASHING / TRIM

- a. Galvanized Steel: 22 gauge thickness.
- B. Downspouts: Fabricate downspouts per plans and details or per size per CA plumbing code. Fabricate from the following materials unless otherwise shown on drawings.
   1. Galvanized Steel: 22 gauge thickness.
- C. Conductor Heads: Fabricate conductor heads with flanged back and stiffened top edge and of dimensions and shape required, complete with outlet tubes, exterior flange trim, and built-in overflows. Fabricate from the following materials:
  - 1. Galvanized Steel: 22 gauge thickness.

#### 7. WALL SHEET METAL FABRICATIONS

- A. Through-Wall Flashing: Fabricate continuous flashings in minimum 96-inch- long, but not exceeding 12-foot long, sections, under copings, and at shelf angles. Fabricate discontinuous lintel, sill, and similar flashings to extend 6 inches beyond each side of wall openings; and form with 2-inch high, end dams. Fabricate from the following materials:
  - 1. Galvanized Steel: 22 gauge thickness.
- B. Opening Flashings in Frame Construction: Fabricate head, sill, jamb, and similar flashings to extend **4 inches** beyond wall openings. Form head and sill flashing with 2-inch high, end dams. Fabricate from the following materials:
  - 1. Galvanized Steel: 22 gauge thickness.
- C. Wall Expansion-Joint Cover: Fabricate from the following materials:
  - 1. Galvanized Steel: 22 gauge thickness.

#### 8. MISCELLANEOUS SHEET METAL FABRICATIONS

- A. Gutters: Fabricate from the following materials:
  - 1. Pre-Finished Steel: 22 gauge thickness.
- B. Downspouts: Fabricate from the following materials:
  - 1. Steel: Schedule 40
- C. Edge Metal / Gravel Stop: Fabricate from the following materials:
  - 1. Pre-Finished Steel: 24 gauge thickness.
- D. Cleat Flashing: Fabricate from the following materials:
  - 1. Galvanized Steel: 22 gauge thickness.
- E. Curb Covers / Pans: Fabricate from the following materials:
  - 1. Galvanized Steel: 22 gauge thickness.

- F. Scuppers: Fabricate from the following materials:
  - 1. Galvanized Steel: 22 gauge thickness.
- G. Equipment Support Flashing: Fabricate from the following materials:
  - 1. Galvanized Steel: 22 gauge thickness.
- H. Overhead-Piping Safety Pans: Fabricate from the following materials:
  - 1. Galvanized Steel: 22 gauge thickness.

#### 3.EXECUTION

#### 1. EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, substrate, and other conditions affecting performance of the Work.
  - 1. Verify compliance with requirements for installation tolerances of substrates.
  - 2. Verify that substrate is sound, dry, smooth, clean, sloped for drainage, and securely anchored.
  - 3. Verify that air- or water-resistant barriers have been installed over sheathing or backing substrate to prevent air infiltration or water penetration.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

#### 2. UNDERLAYMENT INSTALLATION

- A. Self-Adhering Sheet Underlayment: Install self-adhering sheet underlayment, wrinkle free. Prime substrate if recommended by underlayment manufacturer. Comply with temperature restrictions of underlayment manufacturer for installation; use primer for installing underlayment at low temperatures. Apply in shingle fashion to shed water, with end laps of not less than 6 inches staggered 24 inches between courses. Overlap side edges not less than 3-1/2 inches. Roll laps and edges with roller. Cover underlayment within 14 days.
- B. Apply slip sheet, wrinkle free, directly on substrate before installing sheet metal flashing and trim.

#### 3. INSTALLATION, GENERAL

- A. General: Anchor sheet metal flashing and trim and other components of the Work securely in place, with provisions for thermal and structural movement. Use fasteners, solder, protective coatings, separators, sealants, and other miscellaneous items as required to complete sheet metal flashing and trim system.
  - 1. Install sheet metal flashing and trim true to line, levels, and slopes. Provide uniform, neat seams with minimum exposure of solder, welds, and sealant.

- 2. Install sheet metal flashing and trim to fit substrates and to result in watertight performance. Verify shapes and dimensions of surfaces to be covered before fabricating sheet metal.
- 3. Space cleats not more than 12 inches apart. Attach each cleat with at least two fasteners. Bend tabs over fasteners.
- 4. Install exposed sheet metal flashing and trim with limited oil canning, and free of buckling and tool marks.
- 5. Torch cutting of sheet metal flashing and trim is not permitted.
- 6. Do not use graphite pencils to mark metal surfaces.
- B. Metal Protection: Where dissimilar metals contact each other, or where metal contacts pressure-treated wood or other corrosive substrates, protect against galvanic action or corrosion by painting contact surfaces with bituminous coating or by other permanent separation as recommended by sheet metal manufacturer or cited sheet metal standard.
  - 1. Coat concealed side of stainless-steel sheet metal flashing and trim with bituminous coating where flashing and trim contact wood, ferrous metal, or cementitious construction.
  - 2. Underlayment: Where installing sheet metal flashing and trim directly on cementitious or wood substrates, install underlayment and cover with slip sheet.
- C. Expansion Provisions: Provide for thermal expansion of exposed flashing and trim. Space movement joints at maximum of **10 feet** with no joints within 24 inches of corner or intersection.
  - 1. Form expansion joints of intermeshing hooked flanges, not less than 1 inch deep, filled with sealant concealed within joints.
  - 2. Use lapped expansion joints only where indicated on Drawings.
- D. Fasteners: Use fastener sizes that penetrate wood blocking or sheathing not less than 1-1/4 inches for nails and not less than 3/4 inch for wood screws.
- E. Conceal fasteners and expansion provisions where possible in exposed work and locate to minimize possibility of leakage. Cover and seal fasteners and anchors as required for a tight installation.
- F. Seal joints as required for watertight construction.
  - Use sealant-filled joints unless otherwise indicated. Embed hooked flanges of joint members not less than 1 inch into sealant. Form joints to completely conceal sealant. When ambient temperature at time of installation is between 40 and 70 deg F, set joint members for 50 percent movement each way. Adjust setting proportionately for installation at higher ambient temperatures. Do not install sealant-type joints at temperatures below 40 deg F.
  - 2. Prepare joints and apply sealants to comply with requirements in Section 079200 "Joint Sealants."
- G. Soldered Joints: Clean surfaces to be soldered, removing oils and foreign matter. Pretin edges of sheets with solder to width of 1-1/2 inches; however, reduce pre-tinning where pre-tinned surface would show in completed Work.
  - 1. Do not solder metallic-coated steel sheet.
  - 2. Do not pre-tin zinc-tin alloy-coated stainless steel.
  - 3. Do not use torches for soldering.
  - 4. Heat surfaces to receive solder, and flow solder into joint. Fill joint completely. Completely remove flux and spatter from exposed surfaces.

SECTION 07 62 00 - SHEET METAL FLASHING / TRIM

- 5. Stainless-Steel Soldering: Tin edges of uncoated sheets, using solder for stainless steel and acid flux. Promptly remove acid flux residue from metal after tinning and soldering. Comply with solder manufacturer's recommended methods for cleaning and neutralization.
- 6. Copper Soldering: Tin edges of uncoated sheets, using solder for copper.
- Copper-Clad Stainless-Steel Soldering: Tin edges of uncoated sheets, using solder for copper-clad stainless steel.
- H. Rivets: Rivet joints in zinc where necessary for strength.

#### 4. ROOF-DRAINAGE SYSTEM INSTALLATION

- A. General: Install sheet metal roof-drainage items to produce complete roof-drainage system according to cited sheet metal standard unless otherwise indicated. Coordinate installation of roof perimeter flashing with installation of roof-drainage system.
- B. Hanging Gutters: Join sections with riveted and soldered joints or joints sealed with sealant as shown and specified on drawings or summary/scope of work. Provide for thermal expansion. Attach gutters at eave or fascia to firmly anchor them in position. Provide end closures and seal watertight with sealant. Slope to downspouts.
  - 1. Fasten gutter spacers to front and back of gutter.
  - 2. Anchor and loosely lock back edge of gutter to continuous cleat, eave or apron flashing.
  - 3. Anchor back of gutter that extends onto roof deck with cleats spaced not more than 24 inches apart.
  - 4. Anchor gutter with gutter brackets and straps spaced not more than 24 inches apart to roof deck, unless otherwise indicated, and loosely lock to front gutter bead.
  - 5. Anchor gutter with spikes and ferrules spaced not more than 24 inches apart.
  - 6. Install gutter with expansion joints at locations indicated, but not exceeding, 50 feet apart. Install expansion-joint caps.
  - 7. Install continuous gutter screens on gutters with noncorrosive fasteners, removable for cleaning gutters.
- C. Conductor Heads: Anchor securely to wall, with elevation of conductor head rim at minimum of 1 inch below gutter discharge.
- D. Expansion-Joint Covers: Install expansion-joint covers at locations and of configuration indicated. Lap joints minimum of 4 inches in direction of water flow.

#### 5. ROOF FLASHING INSTALLATION

- A. General: Install sheet metal flashing and trim to comply with performance requirements, sheet metal manufacturer's written installation instructions, and cited sheet metal standard. Provide concealed fasteners where possible, and set units true to line, levels, and slopes. Install work with laps, joints, and seams that are permanently watertight and weather resistant.
- B. Roof Edge Flashing: Anchor to resist uplift and outward forces according to recommendations in FM Global Property Loss Prevention Data Sheet 1-49 for FM Approvals' listing for required windstorm classification.
- C. Copings: Anchor to resist uplift and outward forces according to recommendations in cited sheet metal standard unless otherwise indicated.

- 1. Interlock exterior bottom edge of coping with continuous cleat anchored to substrate at 24-inch centers.
- 2. Anchor interior leg of coping with washers and screw fasteners through slotted holes at 24-inch centers.
- D. Copings: Anchor to resist uplift and outward forces according to recommendations in FM Global Property Loss Prevention Data Sheet 1-49 for specified FM Approvals' listing for required windstorm classification.
- E. Pipe or Post Counterflashing: Install counterflashing umbrella with close-fitting collar with top edge flared for elastomeric sealant, extending minimum of 4 inches over base flashing. Install stainless-steel draw band and tighten.
- F. Counterflashing: Coordinate installation of counterflashing with installation of base flashing. Insert counterflashing in reglets or receivers and fit tightly to base flashing. Extend counterflashing 4 inches over base flashing. Lap counterflashing joints minimum of 4 inches. Secure in waterproof manner by means of interlocking folded seam or blind rivets and sealant, anchor and washer at 36-inch centers unless otherwise indicated.
- G. Roof-Penetration Flashing: Coordinate installation of roof-penetration flashing with installation of roofing and other items penetrating roof. Seal with elastomeric sealant and clamp flashing to pipes that penetrate roof.

#### 6. WALL FLASHING INSTALLATION

- A. General: Install sheet metal wall flashing to intercept and exclude penetrating moisture according to cited sheet metal standard unless otherwise indicated. Coordinate installation of wall flashing with installation of wall-opening components such as windows, doors, and louvers.
- B. Through-Wall Flashing: Installation of through-wall flashing is specified in Section 042000 "Unit Masonry."Section092400 "Cement Plastering."
- C. Opening Flashings in Frame Construction: Install continuous head, sill, jamb, and similar flashings to extend 4 inches beyond wall openings.

#### 7. MISCELLANEOUS FLASHING INSTALLATION

- A. Equipment Support Flashing: Coordinate installation of equipment support flashing with installation of roofing and equipment. Weld or seal flashing with elastomeric sealant to equipment support member.
- B. Overhead-Piping Safety Pans: Suspend pans from structure above, independent of other overhead items such as equipment, piping, and conduit, unless otherwise indicated on Drawings. Pipe and install drain line to plumbing waste or drainage system.

#### 8. ERECTION TOLERANCES

A. Installation Tolerances: Shim and align sheet metal flashing and trim within installed tolerance of 1/4 inch in 20 feet on slope and location lines indicated on Drawings and within 1/8-inch offset of adjoining faces and of alignment of matching profiles.

B. Installation Tolerances: Shim and align sheet metal flashing and trim within installed tolerances specified in MCA's "Guide Specification for Residential Metal Roofing."

#### 9. CLEANING AND PROTECTION

- A. Clean exposed metal surfaces of substances that interfere with uniform oxidation and weathering.
- B. Clean and neutralize flux materials. Clean off excess solder.
- C. Clean off excess sealants.
- D. Remove temporary protective coverings and strippable films as sheet metal flashing and trim are installed unless otherwise indicated in manufacturer's written installation instructions. On completion of sheet metal flashing and trim installation, remove unused materials and clean finished surfaces as recommended by sheet metal flashing and trim manufacturer. Maintain sheet metal flashing and trim in clean condition during construction.
- E. Replace sheet metal flashing and trim that have been damaged or that have deteriorated beyond successful repair by finish touchup or similar minor repair procedures.

#### END OF SECTION 07 62 00



© 2006 Garland Industries, Inc.



| FILENAME: RESTOR-FIELD  | FIELD DETAIL                        |
|---|-------------------------------------|
| REINFORCEMENT         FREINFORCEMENT         FREINFORCEMENT         FREINFORCEMENT         FREINFORCEMENT         FREINFORCEMENT         FREINFORCEMENT         FREINFORCEMENT         SMOOTH OR MINERAL SURFACE<br>BUILT-UP OR MODIFIED<br>ROOF SYSTEM         EXISTING DECK | <image/>                            |
| GARLAND COMPANY, INC.   | FIELD DETAIL                        |
| THE GARLAND COMPANY UK, LTD   | SMOOTH/MINERAL MODIFIED RESTORATION |
|   | © 2006 Garland Industries, Inc.     |



THE GARLAND COMPANY UK, LTD

since 1895

# SMOOTH/MINERAL MODIFIED RESTORATION

© 2006 Garland Industries, Inc.

DETAIL

FLASHING DETAIL

SURFACE WITH ALUMINUM -COATING, WHITE COATING OR GRANULES

ROOF RESTORATION COATING



© 2006 Garland Industries, Inc.